



HAL
open science

Environmental contamination in a high-income country (France) by antibiotics, antibiotic-resistant bacteria, and antibiotic resistance genes: Status and possible causes

Marisa Haenni, Christophe Dagot, Olivier Chesneau, Delphine Bibbal, Jérôme Labanowski, Michèle Vialette, Damien Bouchard, Fabrice Martin-Laurent, Louisiane Calsat, Sylvie Nazaret, et al.

► To cite this version:

Marisa Haenni, Christophe Dagot, Olivier Chesneau, Delphine Bibbal, Jérôme Labanowski, et al.. Environmental contamination in a high-income country (France) by antibiotics, antibiotic-resistant bacteria, and antibiotic resistance genes: Status and possible causes. *Environment International*, 2022, 159, pp.107047. 10.1016/j.envint.2021.107047 . hal-03496334

HAL Id: hal-03496334

<https://brgm.hal.science/hal-03496334v1>

Submitted on 20 Dec 2021

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



Distributed under a Creative Commons Attribution - NonCommercial - NoDerivatives 4.0 International License



Environmental contamination in a high-income country (France) by antibiotics, antibiotic-resistant bacteria, and antibiotic resistance genes: Status and possible causes

Marisa Haenni^a, Christophe Dagot^b, Olivier Chesneau^c, Delphine Bibbal^d, Jérôme Labanowski^e, Michèle Vialette^f, Damien Bouchard^g, Fabrice Martin-Laurent^h, Louisiane Calsatⁱ, Sylvie Nazaret^j, Fabienne Petit^{k,1}, Anne-Marie Pourcher^m, Anne Togolaⁿ, Morgane Bachelot^o, Edward Topp^p, Didier Hocquet^{q,r,*}

^a Unité Antibiorésistance et Virulence Bactériennes, ANSES (French Agency for Food, Environmental and Occupational Health & Safety) – Université de Lyon, Lyon, France

^b Université de Limoges, RESINFIT, UMR INSERM 1092, CHU, F-87000 Limoges, France

^c Collection de l'Institut Pasteur (CIP), Microbiology Department, Institut Pasteur, Paris, France

^d INTHERES, Université de Toulouse, INRAE, ENVT, Toulouse, France

^e Université de Poitiers, UMR CNRS 7285 IC2MP, ENSI Poitiers, Poitiers, France

^f Institut Pasteur de Lille, Lille, France

^g National Agency for Veterinary Medicinal Products, ANSES, Fougères, France

^h AgroSup Dijon, INRAE, Université Bourgogne Franche-Comté, Agroécologie, Dijon, France

ⁱ Risk Assessment Department (DER), ANSES (French Agency for Food, Environmental and Occupational Health & Safety), Maisons-Alfort, France

^j Université de Lyon, Université Claude Bernard Lyon 1, UMR CNRS 5557, UMR INRAE 1418, VetAgro Sup, Ecologie Microbienne, F-69622 Villeurbanne, France

^k UNIROUEN, UNICAEN, CNRS, M2C, Normandie Université Rouen, France

¹ Sorbonne Université, CNRS, EPHE, PSL, UMR METIS, Paris F-75005, France

^m INRAE, OPAALE Research Unit, CS 64427, F-35044 Rennes, France

ⁿ BRGM, F-45060 Orléans, France

^o ANSES (French Agency for Food, Environmental and Occupational Health & Safety), Maisons-Alfort, France

^p Agriculture and Agri-Food Canada, and University of Western Ontario, London, ON, Canada

^q UMR Chronoenvironnement CNRS 6249, Université de Bourgogne Franche-Comté, Besançon, France

^r Hygiène Hospitalière, Centre Hospitalier Universitaire, 25030 Besançon, France

ARTICLE INFO

Handling Editor: Frederic Coulon

Keywords:

Antibiotic resistance

One Health

Environmental antibiotic concentrations

Aquatic environment

Terrestrial environment

Wastewater

Organic waste product

ABSTRACT

Antimicrobial resistance (AMR) is a major global public health concern, shared by a large number of human and animal health actors. Within the framework of a One Health approach, actions should be implemented in the environmental realm, as well as the human and animal realms. The Government of France commissioned a report to provide policy and decision makers with an evidential basis for recommending or taking future actions to mitigate AMR in the environment. We first examined the mechanisms that underlie the emergence and persistence of antimicrobial resistance in the environment. This report drew up an inventory of the contamination of aquatic and terrestrial environments by AMR and antibiotics, anticipating that the findings will be representative of some other high-income countries. Effluents of wastewater treatment plants were identified as the major source of contamination on French territory, with spreading of organic waste products as a more diffuse and incidental contamination of aquatic environments. A limitation of this review is the heterogeneity of available data in space and time, as well as the lack of data for certain sources.

Comparing the French Measured Environmental Concentrations (MECs) with predicted no effect concentrations (PNECs), fluoroquinolones and trimethoprim were identified as representing high and medium risk of favoring the selection of resistant bacteria in treated wastewater and in the most contaminated rivers. All other antibiotic molecules analyzed (erythromycin, clarithromycin, azithromycin, tetracycline) were at low risk of resistance selection in those environments. However, the heterogeneity of the data available impairs their full

* Corresponding author at: Hygiène hospitalière, Bâtiment PCBio +3, Centre Hospitalier Universitaire, 3 boulevard Fleming, 25030 Besançon, France.

E-mail address: dhocquet@chu-besancon.fr (D. Hocquet).

<https://doi.org/10.1016/j.envint.2021.107047>

Received 4 October 2021; Received in revised form 9 December 2021; Accepted 11 December 2021

Available online 16 December 2021

0160-4120/© 2021 The Authors. Published by Elsevier Ltd. This is an open access article under the CC BY license (<http://creativecommons.org/licenses/by/4.0/>).

exploitation. Consequently, we listed indicators to survey AMR and antibiotics in the environment and recommended the harmonization of sampling strategies and endpoints for analyses.

Finally, the objectives and methods used for the present work could comprise a useful example for how national authorities of countries sharing common socio-geographic characteristics with France could seek to better understand and define the environmental dimension of AMR in their particular settings.

1. Introduction

1.1. Context

The development of resistance of bacterial pathogens to antibiotics has greatly complicated the treatment of life-threatening bacterial infections (Cassini et al., 2019; Furuya and Lowy, 2006; O'Neill, 2014). If antimicrobial resistance (AMR, specifically meaning resistance of bacterial commensals or pathogens to antimicrobial drugs) development proceeded at the current rate, it is predicted that “if no action is taken”, drug resistant infections will account for 10 million global deaths each year by 2050, outpacing those caused by cancers (O'Neill, 2014). Within this context, national and international authorities have developed and are deploying action plans to mitigate the development of AMR (Comité interministériel pour la santé, 2016; European Commission, 2017; WHO et al., 2020; World Health Organization, 2015). These action plans generally have four pillars: surveillance, stewardship, infection prevention and control, and research and innovation. Antibiotics are widely used in human and animal medicine and in food animal production (Klein et al., 2018; Van Boeckel et al., 2015). Under the pressure of antibiotic selection, AMR develops in medicated people and in food animals (Furuya and Lowy, 2006). Additionally, antimicrobial-resistant bacteria commensal or pathogenic for humans (ARB) are thought to be exchanged between humans and animals through direct or indirect transmission via the food chain or the environment (Hernando-Amado et al., 2019). The linkage between animals and humans, and the importance of the environment in facilitating this linkage, has been coined the One Health Framework (Hernando-Amado et al., 2019). Hotspots for AMR development and potential transmission routes of

ARB across the One Health continuum are illustrated in Fig. 1.

It is generally recognized that, in order to be successful, strategies to mitigate the development and the transmission to humans of ARB will require concerted action across the One Health continuum, *i.e.* in human and animal sectors and the environment (Cassini et al., 2019; Comité interministériel pour la santé, 2016; European Commission, 2017; WHO et al., 2020; World Health Organization, 2015). The key objective in both human medicine and agricultural production is clearly to reduce the use of antibiotics to the minimum necessary, in order to reduce selection pressure and prevent AMR development in humans and food animals (Berendonk et al., 2015; Cantas et al., 2013; Hernando-Amado et al., 2019; Ter Kuile et al., 2016; Törneke et al., 2015). On the other hand, taking into account the role of the environment in the development and transmission of AMR is recent, and actions in the environmental sector are currently the least implemented in the framework of public policies (European Commission, 2019; Munkholm et al., 2021; Singer et al., 2016).

Within this context, the French Government commissioned a detailed report on the state of AMR in the aquatic and terrestrial environments of this country based on the One Health approach. The full report was released in November 2020 (Anses, 2020a). We slightly updated its conclusions due to the recent publication of PNEC values (Murray et al., 2020).

The overall objective of this report was to provide policy and decision makers with an evidential basis for recommending or taking future actions to mitigate AMR in the environment. We suggest that the objectives and methods used for this present work could comprise a useful example for how national authorities elsewhere could seek to better understand and define the environmental dimension of AMR in their




Fig. 1. The flow of antimicrobial resistance and antibiotics across the One Health continuum of food-producing animals, humans, and the environment. Grey arrows indicate flow of resistance genes and resistant bacteria; blue arrows indicate flow of antibiotic residues.

particular settings. Important characteristics of France that were taken into account in this review include climate, governance, management of waste streams, agriculture practices, determinants of health and high-income setting. Consequently, the French situation is applicable to countries that share similar attributes; the more variance from these characteristics, the less applicable the analysis will be.

1.2. Geographical and health characteristics of France

The significance of the environment for AMR development and transmission is influenced by climate and landscape, and numerous societal, cultural, economic, and regulatory factors (Collignon et al., 2018). These need to be taken into account in order to understand how far the conclusions reached in this national analysis can or cannot be extrapolated to other settings.

Metropolitan France is located in Western Europe with a surface area of about 641,000 km², about 0.86% of which is water. The climate is variable across the country with mean annual temperatures ranging from 0.2 °C to 28.3 °C and annual precipitation from 523 mm to 1,932 mm (data from MétéoFrance – see Appendix B).

In 2019, *per capita* income was about US\$40494 (Worldbank, 2019). The country has 67 million citizens, most of whom reside in large urban centers. France is a high-income country with excellent water sanitation and hygiene infrastructure. Safe potable water is ubiquitous. Nearly 85% of households are connected to a wastewater treatment plant (WWTP), providing a total treatment capacity of 100 million-population equivalents (PE). Around 80% of WWTPs are of low capacity (<2000 PE), of which 62.5% are of very low capacity (<500 PE). In contrast, 6% of WWTPs have a capacity ≥ 10,000 PE and account for more than 80% of the total capacity of WWTP in France (Commissariat général au développement durable, 2019). Hospitals, health care institutions, and other public infrastructures are connected to these WWTPs, so that they are key elements for the discharge of AMR of human origin (Goulas et al., 2020). The rest of the population (15%) lives in houses connected to on-site wastewater treatment facilities.

In 2014, French agriculture represented 24% of the total European agricultural production (La Représentation permanente de la France auprès de l'Union Européenne, 2021) and was the world's third largest exporter of agricultural goods. Bovine, poultry, and swine production respectively accounted for 9.9%, 5%, and 4.3% of the total French agricultural production. The distribution of these three farming types is highly heterogeneous over the French territory, with intensive pig and poultry farming in the northwestern part of the country, and the rare occurrence of farms in the southeast region. Antibiotics sold to treat livestock reached around 117 tons for bovines, 140 tons for swine, and 73 tons for poultry, with global exposition of animals decreasing dramatically since 2011 (−25.5% for bovines, −60.5% for poultry, −54.0% for swine) (Anses, 2020b).

France has many characteristics that are shared by other European and North American countries. According to the State of Health in the EU initiative, the French healthcare system provides good access to high quality care. Preventable mortality by treatment is one of the lowest in the EU, which indicates that the health system protects people suffering from acute conditions. Antibiotic use in agriculture and in human medicine is regulated by national and European legislation (Journal officiel de la République Française, 2015, 2016). Notable common features are that access to antibiotics for both human and animal health is by prescription only with no over-the-counter sales. In 2019, antibiotic consumption in France for human medicine was among the highest in Europe, with 23.3 defined-daily doses of antimicrobials for systemic use per 1000 inhabitants and per day in the community (which ranged from 8.7 to 32.4 in Europe) (ECDC). There is currently essentially no domestic manufacturing of antibiotics.

1.3. Objectives

The objectives of this work were to gather available information concerning the current state and key drivers of AMR in the environment of France. First, we give an overview of the mechanisms underlying the emergence and persistence of AMR in the environment. Second, we drew up an inventory of current knowledge concerning the contamination of the terrestrial and aquatic environmental compartments by antibiotic residues and resistance to antibiotics (ARB, and antibiotic resistance genes – ARGs) and their spatial and temporal distribution. Third, we identified the antibiotics at risk to select AMR in the environment of France. Finally, we recommend avenues to improve and broaden our knowledge on the burden of AMR in the environment of this country.

2. Methods

2.1. Working group

In November 2016, the three Directorate Generals for Risk Prevention, Health, and Food Safety requested the advice of the French Agency for Food, Environmental and Occupational Health & Safety (ANSES) on the theme 'Antimicrobial resistance and the environment'. It is an administrative public establishment accountable to the French Ministries of Health, Agriculture, the Environment, Labor and Consumer Affairs. The Director General of ANSES created a working group to answer this question and has launched a call for interested experts. ANSES chose the experts based on their field of expertise and availability, seeking a balance of disciplines; fundamental, clinical, veterinary, environmental microbiology, and residue chemistry. The experts attested their independence through a public declaration of potential conflicts of interest, available on the website of the French Ministry of Health (dpi.sante.gouv.fr).

2.2. Data and method of expertise

The expertise was based on data and knowledge obtained from published scientific literature searched using PubMed and ScienceDirect, institutional reports on water, soils, and bacteria. Concerning more specifically the environmental concentrations of antibiotics, peer-reviewed literature, databases from research programs and surveillance databases on the French water resources were used (detailed in Appendix B).

The expertise was carried out in compliance with the standard NF X 50-110 "Quality in expertise - General requirements for expertise (May 2003)". This expertise focused on aquatic and terrestrial environments and their sources of contamination in metropolitan France and French overseas departments and regions. The environmental concentrations of antibiotics and the environmental distribution of ARB and ARGs of human health concern were considered, regardless of their method of quantification. Animal pathogens, environmental commensal bacteria, and genes conferring resistance to antibiotics that are not used in human medicine were not considered in the analysis. Where relevant, or to compensate for a lack of French data, environmental contamination measured elsewhere in Europe and in Canada was used for comparison. Aspects of the expertise concerning the conceptual basis of the spread of AMR drew on international literature. Likewise, this review does address conditions that could favor the transfer of ARGs from environmental bacteria to human pathogenic bacteria.

2.3. Investigated compartments

In high-income countries such as France, the main sources of environmental contamination with ARB and antibiotic residues are human and animal fecal waste inputs. Consequently, potential hotspots are treated wastewater effluents, fertilizers of human or animal fecal origin, and fish farm effluents (Gordon et al., 2007; McKinney et al., 2018;

Pruden et al., 2013; Quintela-Baluja et al., 2019). Leaking septic systems (Schaider et al., 2017) and effluent from landfill sites can also be a source of contamination but, in the absence of national data, these sources of contamination were excluded from the scope of this review.

Fig. 2 illustrates the sources and dissemination pathways of contamination in the main receiving environmental compartments considered; namely aquatic environments (including surface water, groundwater, and coastal water), terrestrial environments (including soils and plants), and wildlife.

3. Mechanisms underlying the emergence and persistence of antimicrobial resistance in the environment

Our understanding of the mechanisms involved in the emergence and persistence of AMR have generally been informed through gene mutation and transfer experiments carried out in the laboratory (Baharoglu and Mazel, 2011; Gullberg et al., 2014). Such experiments usually investigate the interactions of single antibiotics on single bacterial species, or bacterial mixtures of moderate complexity. Recently, the SELECT method (SElection End points in Communities of bacTeria) has been implemented to determine PNECs of antibiotics in complex microbial community (Murray et al., 2020). The findings are assumed to reflect what happens *in situ*, but the physical, chemical, and biological complexity of the terrestrial and aquatic environments cannot be fully replicated in the laboratory. In addition, nor can the effects of environmental exposure to complex and varying mixtures of selective and potential co-selective substances typical of waste streams be considered. Some of the challenges and unknowns this complexity represents are considered in the following sections.

3.1. At the scale of the bacterium

At the cellular level, the bacterial response induced by an antibiotic will vary according to the exposure dose and the bacterial species in question. It is generally accepted that maintenance of an ARG represents a fitness cost that puts the resistant bacterium at a competitive disadvantage relative to its susceptible parent (Melnik et al., 2015). This disadvantage can be remedied through compensatory mutations that counterbalance the fitness cost (Andersson and Hughes, 2014) or external factors such as the presence of sub-inhibitory concentrations of antibiotics, *i.e.* concentrations below the minimum inhibitory concentration (MIC). These low concentrations may promote the emergence and persistence of ARGs by: (i) inhibiting the growth of antibiotic-susceptible populations and thus promoting the maintenance of antibiotic-resistant populations (defining the Minimum Selective Concentration, MSC); (ii) favoring the accumulation of mutations of low biological cost allowing bacteria to reach low-level resistance to different classes of antibiotics (Gullberg et al., 2011); (iii) inducing the SOS response, which in turn accelerates horizontal transfer of ARGs through transduction or conjugation (Jutkina et al., 2018; Ross and Topp, 2015) and decreases DNA replication fidelity, thus increasing the frequency of mutations affecting, among others, genes implicated in antibiotic resistance (Baharoglu and Mazel, 2014).

Data on the cumulative effects of simultaneous exposure to several selective agents are very scarce. However, a combination of biological effects of mixtures of selective agents present in the environment may be strongly suspected since: (i) co-selection of a bacterial clone co-resistant to several selective agents can be achieved by each of the selective agent to which the clone is resistant (Murray et al., 2019), and (ii) mechanisms




Fig. 2. Main sources and contamination routes of soil and water by antibiotic-resistant bacteria and antibiotic residues. WWTP, wastewater treatment plant.

of resistance to heavy metals and biocides can confer resistance to antibiotics (Nishino et al., 2007). This phenomenon is called cross-resistance.

3.2. At the scale of the bacterial community

Within a population or community, bacteria can cooperate to resist the actions of an antibiotic, for example through the formation of protective structures such as biofilms (Vega and Gore, 2014; Wright, 2005), whose formation can be favored by bacterial exposure to sub-inhibitory concentrations of antibiotics. It is generally accepted that the majority of bacteria in practically all environments are integrated into biofilms (Flemming et al., 2016). Biofilms can be extremely heterogeneous in structure, chemical and bacterial community compositions. Gradients of pH, oxygen and other electron acceptors and organic nutrients can be abrupt and highly dynamic, creating distinct microenvironments (Flemming and Wingender, 2010). Bacteria living in biofilms may be more resistant to antibiotics than the same bacteria in the planktonic state for several reasons (Flemming et al., 2016). First, the biofilm matrix constitutes a physical barrier to the penetration of antibiotics. Second, nutrient depletion in these microenvironments leads the bacteria to a viable but non-culturable (VBNC) or persistent state, which may reduce their sensitivity to antibiotics (Ayrapetyan et al., 2018; Fisher et al., 2017). Third, community cooperation could occur, for example allowing β -lactam-susceptible bacteria to survive in close proximity to individuals producing β -lactamases that hydrolyze these antibiotics. Within such multicellular structure, should at least one bacterial species of the community produces an enzyme that deactivates an antibiotic, bacteria susceptible to that antibiotic are protected by such 'public good' resistance mechanisms (Meredith et al., 2015). And finally, expression of quorum sensing can indirectly impact resistance to antibiotics (Hoffman et al., 2005; Nalca et al., 2006).

ARGs are often carried on plasmids, which intra- and inter-species dispersal can be spurred by the exposure to an antibiotic. Thus, even though the fraction of a community that carries a plasmid may be extremely small in the absence of antibiotic pressure, should antibiotic pressure be applied ARGs will be dispersed through the community after conjugative transfer of the plasmid (Lopatkin et al., 2017; San Millan and MacLean, 2017).

For all these reasons, the environmental risk assessment (ERA) of antibiotics in the environment and their potential to select for AMR cannot only rely on the testing of isogenic bacterial cultures with gradients of selective agents. Instead, the determination of PNECs must rely on methodological approaches dealing with mixed bacterial communities (Murray et al., 2021).

3.3. Mechanisms that govern bioavailability and bioaccessibility of antibiotic

Bioaccessibility expresses a constraint in time and/or space, linked to habitat, and has to be considered, in particular, in complex matrices such as soils or sediments, where the vast majority of bacteria are in biofilms which, among others, provide a physical barrier preventing the entry of antibiotics (see above) (Flemming et al., 2016). Bioavailability depends on intrinsic physicochemical properties of the active compound and is influenced by the environmental conditions and interactions with the surrounding matrix. For example, cation exchange and/or cation bridging mechanisms between the charged moieties of fluoroquinolones and cations result in a reduced bioavailability of these antibiotics. Fluoroquinolones form strong surface complexes with many transition metal ions through the carboxyl group and ring carbonyl oxygen (Gu and Karthikeyan, 2005). Also the presence of the divalent inorganic cations Mg^{2+} and Ca^{2+} , which are widely abundant in water, reduces the bioavailability of tetracycline by forming stable tetracycline-metal complexes (Werner et al., 2006; Zhang et al., 2018). Some macrolides are also affected by the presence of hydrated cations (Ca^{2+} , Na^{+}) that

may act as proton-donors. Macrolides and tetracycline speciation are also strongly influenced by their association with dissolved organic matter (Chen et al., 2015; Sibley and Pedersen, 2008). In extremely complex matrix such as soil whose physicochemical properties (pH, content and nature of organic matter, cation exchange capacity) are highly variable, the possibility of predicting the concentration of bioavailable antibiotics and then exposure of living organisms is limited (Menz et al., 2018; Sidhu et al., 2019).

3.4. Transfer of ARGs to pathogenic bacterial species in the environment

Environmental microbial communities constitute a reservoir of ARGs, whose diversity and abundance remains largely unknown, and that have the potential to be acquired by pathogenic bacteria via mobile genetic elements (Nesme and Simonet, 2015). It is indeed known that several ARGs that have emerged in human bacterial pathogens, such as *bla*_{CTX-M} and *mcr-1* genes, originated from environmental or commensal bacteria (Bonnet, 2004; Kieffer et al., 2017). Considering that the selection of a new ARB is more likely in an environment contaminated by one or more antimicrobial compounds, environments enriched with autochthonous bacteria, allochthonous potential pathogenic bacteria and selective antimicrobial compounds would be possible hotspots for the selection of new ARB equipped with new ARGs. The evolution of resistance to antibiotics in bacterial biofilm communities would be faster than in planktonic communities, since the physical proximity of the bacterial populations within the biofilm facilitates the horizontal transfer of genes by conjugation (Arias-Andres et al., 2018; Arias-Andres et al., 2019; Balcázar et al., 2015). While horizontal gene transfers are major drivers of bacterial evolution, their rates strongly depend on surrounding conditions; in that frame, transfers of new ARGs to pathogens and their subsequent maintenance and dissemination are likely rare.

Anthropogenic activities favor the diversification of ARGs and their dissemination in phylogenetically distant bacterial species. Fig. 3 summarizes conditions favoring the emergence of pathogenic bacterial strains carrying new ARGs of environmental or clinical origin in aquatic or terrestrial receiving environments. The probability of this emergence increases with the intensity of environmental contamination by pathogenic bacteria and depends on the presence of selective agents, which is




Fig. 3. Environmental conditions favorable to the transfer of antibiotic resistance genes to pathogenic bacterial species. MSC, minimal selective concentration.

discussed hereafter.

4. Environmental contamination by antibiotics in France

Surveillance of antibiotic residue concentrations in the environment of France has historically been limited in scope. Given the small number of environmental samples evaluated, heavily biased by the over-representation of surface water samples, and the few antibiotics analyzed, only a limited overview of the environmental contamination

by antibiotics in France can be reported (Supplemental Table 1). Despite these constraints, the most frequently quantified antibiotics in soil, organic waste products (OWPs, including sewage sludges and animal fecal waste) and water in France belong to the quinolone, fluoroquinolone, macrolide, and sulfonamide families, which are environmentally persistent (Boxall et al., 2004). Though β -lactams are the most widely consumed antibiotics in human medicine (Moulin et al., 2008), they are rarely found in the environment due to their ready degradability (Supplemental Table 1).




Fig. 4. Concentration of antibiotics from different pharmacological classes in the dissolved phases of treated wastewater, surface and groundwater (A) and in aquatic sediments and periphytons (B) in France. Box plots indicate min, P25, median, P75 and max of antibiotic concentrations (left y-axis). The crosses indicate the frequencies of quantification (right y-axis). The antibiotics considered are those for which sufficient data were available for all the matrices (we chose an arbitrary cutoff of 10 data points). We substituted results below the analytical limit with half of the detection limit value. CIP, ciprofloxacin (fluoroquinolone); SMX, sulfamethoxazole (sulfonamide); TMP, trimethoprim; ERY, erythromycin (macrolide); FLU, flumequine (quinolone); OTC, oxytetracycline (tetracycline); N, number of samples; DM, dry matter (Aubertheau-Laurent, 2013; Azimi et al., 2018; Camilleri et al., 2015; Capdeville, 2011; Chonova et al., 2016; Chonova et al., 2018; Coetsier et al., 2009; Dinh et al., 2017a; Feitosa-Felizzola and Chiron, 2009; Garcia-Armisen et al., 2013; Guibal et al., 2018; Joigneaux, 2011; Mailler et al., 2015; Tamtam et al., 2008; Wiest et al., 2018).

As observed in other countries, the antibiotics found in the environment come from anthropogenic sources, mainly treated or untreated wastewater, and agricultural discharges. Their continuous input into receiving environments and their persistence account for the ubiquity of some antibiotics. Nevertheless, in France, antibiotic concentrations are generally low in water, sediments and soils (Supplemental Table 1). This is not the case in countries devoid of or badly equipped with sanitation systems, and to industrial regions of antibiotic-producing countries (e.g. India, China) (ChangingMarkets, 2016).

4.1. Aquatic environments and sources of contamination

Fig. 4 presents the concentrations of the six most frequently analyzed antibiotics in treated wastewater and in the receiving compartments of aquatic environments as reported in the peer reviewed literature and collected by national study sites (SIPIBEL, PIREN; see Appendix B).

These data show that WWTP discharges are a major source of antibiotics in aquatic environments in France (Fig. 4A) (Capdeville, 2011; Oberlé et al., 2012; Ory et al., 2016; Perrodin et al., 2013). Beside this major human source of water contamination, spreading of OWP as fertilizers (see 4.2 on terrestrial contamination) can also ultimately contribute to a more diffuse and incidental contamination of aquatic environments due to runoff, leaching and/or infiltration (Charuaud et al., 2019).

Concentrations of antibiotics in the dissolved phase of surface water decrease with distance from the WWTP discharge point due to dilution, degradation, and sorption to particulate matter. Concentrations can vary seasonally due to changes in river flow rates and water temperature, and from precipitation events that drive combined sewer outflows, releasing untreated wastewater into receiving bodies (Alygizakis et al., 2016; Baker and Kasprzyk-Hordern, 2013; Batt et al., 2006).

Antibiotic concentrations are usually less than 100 ng.g DM⁻¹ in sediment and periphyton (Fig. 4B). The frequency of detection and median concentrations are generally higher in periphyton than in sediments, but the highest concentrations have been reported in sediments (Aubertheau et al., 2017; Labadie et al., 2019; Vivant et al., 2015). The concentrations of antibiotics in the sediment increase with proximity to sewage outflows (Labadie et al., 2019). Antibiotics stored in sediments may be remobilized during extreme hydrological events (Heß et al., 2018). The cooler and more reducing conditions in sediments are associated with poor biodegradation rates and the accumulation of persistent antibiotics such as fluoroquinolones, macrolides, and sulfonamides (Tamtam et al., 2011b; Thiebault et al., 2021). Indeed, along a




Fig. 5. Median concentrations of ciprofloxacin and sulfamethoxazole and proportion of samples above the limit of detection along the contamination continuum. The numbers of samples for ciprofloxacin and sulfamethoxazole are indicated in brackets, in this order). See Supplemental Table 1 for details. We substituted results below the analytical limit with half of the detection limit value. The labels on top of the bars give the proportion of samples above the limits of detection (LOD; 6 ng.L⁻¹ for ciprofloxacin and 10 ng.L⁻¹ for sulfamethoxazole (Patrolecco et al., 2018)).

sediment core corresponding to several decades of accumulation, antibiotic concentrations reflected the persistence properties of the antibiotics and the time of their market authorization (Tamtam et al., 2011b; Thiebault et al., 2021; Thiebault et al., 2017). Although traces of sulfamethoxazole have been measured in groundwater (Lopez et al., 2015; Vulliet et al., 2011), other antibiotics are only exceptionally quantified in this matrix (Supplemental Table 1).

Fig. 5 illustrates the decrease in the concentration of antibiotics and their frequency of quantification along the contamination continuum from a hospital. Taking ciprofloxacin and sulfamethoxazole as examples, we found that WWTPs reduce the concentrations of these antibiotics by 1.1–2.5 Log₁₀ and that concentrations in surface water are 0.7–1.3 Log₁₀ lower than in treated wastewater. Ciprofloxacin was rarely (≤1%) detected in the dissolved phase of surface water and groundwater. The detection of sulfamethoxazole in these matrices was more frequent (3–27%). Overall, the median concentrations of these antibiotics were ≤ 5 ng.L⁻¹ in the dissolved phase of surface water and groundwater.

4.2. Terrestrial environments and sources of contamination

Antibiotics are entrained into soil with the application of OWPs. Fig. 6 presents the concentrations measured for six antibiotics in France in WWTP sludge, solid manure, and soils amended with OWP. Each year, France produces 729 million tons (Mt) of OWPs. Of the 300 Mt of OWPs spread on fields yearly, a minority (1.1 Mt) are sludges produced by WWTPs and the vast majority (94%) are livestock effluents. Overall, 6.6 Mha of field crops and grasslands are amended with OWPs, representing 24.6% of the useful agricultural area in metropolitan France (Ademe, 2018). However, since the different farming types are heterogeneously distributed in France, soils are also heterogeneously amended over the territory (Houot et al., 2014).

Quinolones and fluoroquinolones are the most frequently quantified antibiotics and those with the highest concentrations in WWTP sludge (median concentrations between 2,600 and 3,000 ng.g DM⁻¹ for each ofloxacin, ciprofloxacin, and norfloxacin). The other antibiotics are found at median concentrations lower than 62 ng.g DM⁻¹ (Fig. 5 and Supplemental Table 1) (Bourdat-Deschamps et al., 2017).

The data on manure slurry, as commonly managed in the dairy and swine sectors, are scarce. Liquid OWPs seemed to be less contaminated with antibiotics than solid farm OWPs. Hence, the mean concentrations of ciprofloxacin were 241 ng.g DM⁻¹ and 6 ng.L⁻¹ and those of doxycycline were 11,898 ng.g DM⁻¹ and 505 ng.L⁻¹ in solid and liquid farm OWPs, respectively (Fig. 6).




Fig. 6. Concentrations of six antibiotics from different pharmacological classes measured in OWPs (sewage sludges and solid farm products) and in OWP-amended soils in France. The antibiotics considered are those for which the largest amount of data was available in their pharmacological class, for all the considered matrices. Concentrations are presented as box plots (min, P25, median, P75, and max; left y-axis) and quantification frequencies as crosses (right y-axis). Results below the analytical limit were substituted by half of the detection limit value. All the dosage of ERY in solid farm product ($n = 4$) were below the LOD and not represented. CIP, ciprofloxacin (fluoroquinolone); SMX, sulfamethoxazole (sulfonamide); TMP, trimethoprim; ERY, erythromycin (macrolide); FLU, flumequine (quinolone); OTC, oxytetracycline (tetracycline); OWPs, Organic Waste Products; N, number of samples; DM, dry matter. For amended soils: (Bourdat-Deschamps et al., 2017; Dinh et al., 2017b; Nazaret, 2020a,b; Salvia et al., 2015; Salvia et al., 2012; Tamtam et al., 2011a); for farm solid OWP: (Algros and Jourdain, 2007; Bourdat-Deschamps et al., 2017; Moraru et al., 2012; Nazaret, 2020a,b; Pourcher et al., 2014; Simonet and Gardeur-Algros, 2012); for sewage sludges: (Algros and Jourdain, 2007; Bourdat-Deschamps et al., 2017; Simonet and Gardeur-Algros, 2012; Tamtam et al., 2009).

The median concentrations for antibiotics quantified at least once in OWP-amended agricultural soil do not exceed 2.1 ng.g DM^{-1} , with the nature of the antibiotics depending on the type and source of OWPs. The temporal variations of concentrations depend on the periodicity of enrichment with OWPs. Surface application of manure generally results in higher antibiotic levels in runoff than do injection or incorporation (Joy et al., 2013). However, periods of more than two weeks between spreading and rain events reduce antibiotic levels in runoff (Barrios et al., 2020).

Although the overall consumption of antibiotics is known in human (728 tons/year in 2018) and animal (471 tons/year in 2018) health (Santé Publique France et al., 2019), the estimation of the amount of antibiotics reaching the environment is nearly impossible. Hence, the *in vivo* metabolism, the *ex vivo* stability, the solubility of the antibiotic compounds are too diverse to allow any trustable estimation. The difference in the nature and the duration of treatments of OWPs prior to spread on fields, and the fact that only a fraction of the OWPs are used as fertilizers further complicates the task.

5. Contamination by ARB and ARGs

In France, as in all industrialized countries, ARB and ARGs are detected in all terrestrial and aquatic environments subjected to anthropogenic pressures (Buelow et al., 2020; Kümmerer, 2004). The vulnerability of water and soil to contamination is primarily related to exposure to fecal waste streams (Servais and Passerat, 2009; Zhu et al., 2019). Surface water is prone to contamination from both point sources (e.g. WWTP discharges) and non-point sources (e.g. runoff from OWP-amended fields) (Bréchet et al., 2014; Buelow et al., 2020; Dinh et al., 2017a; Drieux et al., 2016; Henriot et al., 2019; Labadie et al., 2019; Laroche et al., 2010; Oberlé et al., 2012; Ratajczak et al., 2010).

There is a paucity of French data for certain sources (e.g. manure, sludge, aquaculture) and for some environmental compartments (i.e. aquifers, coastal zones, soils, rhizosphere, phyllosphere, wildlife).

5.1. ARB and ARGs in wastewater effluents

Contamination of water by ARB and ARGs of human and animal origin can be reduced by natural attenuation. Their dissipation rate in the water environment will depend on biotic or abiotic parameters including the dilution in the receiving environment as well as protozoan predation, viral lysis, and ability of ARB to overcome environmental stresses (Rozen and Belkin, 2001; van Elsas et al., 2011). However, this attenuation is no longer observed in areas subject to continuous and significant inputs of ARB, ARGs, and selective agents, such as sediments or biofilm at close proximity to a WWTP discharge (Aubertheau et al., 2017; Fairbairn et al., 2016; Leclercq et al., 2013; Oberlé et al., 2012). In these polluted areas, the persistence of AMR could be favored by the high concentrations of selective agents (Fig. 4) so that the rate of AMR contamination could, at least in part, compensate that of dissipation.

Globally, most WWTPs only use primary and secondary treatment, without downstream treatments such as ultrafiltration or UV treatment. These WWTPs reduce the concentration of fecal bacteria and the concentration of ARGs in treated effluent by about 2 Log_{10} (Stalder et al., 2014). Indeed, the Log_{10} reduction of ESBL-producing *E. coli* and vancomycin-resistant enterococci are 1.5 and 2.5 Log_{10} , respectively, consistent with the Log_{10} reduction of their susceptible parents (Bréchet et al., 2014; Galvin et al., 2010; Gouliouris et al., 2019; Leclercq et al., 2013; Oberlé et al., 2012; Servais and Passerat, 2009; Slekovec et al., 2012; Varela et al., 2013). The few available data on slaughterhouse effluents in France come from beef slaughterhouses. Effluents from calf slaughterhouses are more concentrated in antibiotic-resistant *E. coli* than those from adult cattle slaughterhouses (Um et al., 2016). The functioning and efficiency of slaughterhouse WWTPs are comparable to urban WWTPs (Bibbal et al., 2014).

In order to assess the spread of AMR independently from culture methods, *intI1* concentration has been proposed as a proxy for anthropogenic contamination (Gillings et al., 2014). Hospital effluents contain about 10 times more copies of *intI1* ($\sim 10^{11}$ copies.L⁻¹) than urban wastewater. Although their volume is very much lower than that of the

urban community in which they are collected (Stalder et al., 2014), hospital effluents have much more abundant ARB than household sewage (Buelow et al., 2018; Buelow et al., 2020). There is a larger diversity of ARGs in domestic raw sewage than in hospital wastewater (Buelow et al., 2020), the latter are enriched in genes encoding resistance to hospital-specific antibiotics, for example *acaA4* and *aadB* that confer resistance to aminoglycosides (Stalder et al., 2014).

5.2. ARB and ARGs in surface and ground water

The vast majority of fecal ARB found in aquatic environments come from anthropogenic sources. The presence of ARB and ARGs in aquatic environments depends on recurrent emissions of fecal bacteria from WWTP discharges. For instance, concentrations of ESBL-producing *E. coli* increased from 20 CFU.L⁻¹ upstream to 1,300 CFU.L⁻¹ downstream of the WWTP of a 120,000 inhabitant city (Bréchet et al., 2014). In addition, runoff from agricultural areas amended with OWPs and overflow from combined sewage collection systems during heavy rainfall can also contribute to the contamination of surface water. Spatial dynamics in contamination by fecal ARB and their corresponding ARGs, could be observed in water column, biofilm or sediment sampled along a river continuum, from the effluent discharge point to downstream. For instance, the proportion *intI1*/16S rRNA reached 1.89.10⁻¹ in the River Seine downstream the city of Paris, while went back to 10⁻³ at the estuary of the river (Aubertheau et al., 2017; Dinh et al., 2017b; Fairbairn et al., 2016; Leclercq et al., 2013; Oberlé et al., 2012; Petit et al., 2017). Indeed, studies reported the disappearance of specific populations of fecal ARB (*E. coli* and *Enterococcus faecium*) in favor of other populations of the same bacterial species, less resistant to antibiotics but probably better adapted to the aquatic environment (Berthe et al., 2013; Martak et al., 2020). In groundwater, mainly karst hydrosystems, the occurrence of ARB of fecal origin is depending on the hydrological conditions and the land use (pasture and manure application). Overall, antibiotic-resistant *E. coli* were rarely detected at the drilling of this groundwater used for the production of drinking water, except during major rainfall events (Laroche et al., 2010; Ratajczak et al., 2010; Ribeiro et al., 2012).

5.3. ARB and ARGs in organic waste products

Two French studies have quantified ARB or ARGs in OWPs and evaluated how they vary according to the treatment. These studies were focused only on manure and confirmed observations from other countries where OWPs underwent similar treatments (Le Devendec et al., 2016; Moraru et al., 2012). For example, Moraru et al. in France and Sharma et al. in Canada observed a decrease in concentrations (>3 Log₁₀) of antibiotic-resistant *E. coli* during chicken litter storage and during composting of cattle manure, respectively (Moraru et al., 2012; Sharma et al., 2009).

Le Devendec et al. reported that broiler manure composting has little impact on the relative abundance of some ARGs (e.g. *sul2*), but significantly decreased (3.7–4.7 Log₁₀) the abundance of others (e.g. *tet(M)*, *erm(B)*) (Le Devendec et al., 2016). Canadian studies reported that treatments applied to manure (composting, dewatering) or to WWTP sludge (lime stabilization, thermal treatment) reduced the abundance of ARGs, reducing the risk of transmission of ARGs to crops or water resources (Lau et al., 2017; Murray et al., 2019; Tien et al., 2017). Clearance of ARGs depends on the treatment applied to the matrix. Hence, the concentration of eight ARGs in heat-treated pellets were 1–1.5 Log₁₀ lower than in anaerobically-digested sewage sludge and 1.3–2.2 Log₁₀ lower than in aerobically digested biosolids (Lau et al., 2017). Similarly, by testing ten ARGs, Tien et al. found that digested, dewatered, and composted manure contained concentrations of ARGs 0.8–3 Log₁₀ lower than in raw manure (Tien et al., 2017).

5.4. ARB and ARGs in soil

Very few studies measured soil contamination by ARB and ARGs in France, with most of them being unpublished. In agreement with data reported in other countries, these studies described the common presence of ARB and ARGs within the bacterial communities of agricultural, corroborating the status of these soils as an environmental reservoir. As an illustration, Hartmann et al. detected isolates of CTX-M–1–producing *E. coli* both in cultivated soil in Burgundy amended one year earlier with manure, and in grassland soil sampled in the vicinity of dairy farms (Hartmann et al., 2012). Some isolates shared the same genotype than those found in animals from these farms, suggesting the long-term persistence of the isolates from animal origin after manure application. An on-going French study showed that the persistence of ARGs depends on many factors (i.e. climate, topology of the amended fields, soil type, frequency of application, characteristics of the manure applied, and composition of the soil bacterial communities). However, the same study found that the absolute abundance of ARGs (i.e. *sul*, *intI1*, *tet*) (i) increased by 1 to 2 Log₁₀ one month after bovine manure application, and (ii) generally did not increase over the long term in amended plots despite repeated applications (personal data, S. Nazaret). In field experiments conducted in Canada, the kinetics of ARG dissipation in soil after land spreading was similar regardless of pre-application treatment (Lau et al., 2017; Murray et al., 2019; Tien et al., 2017). Consequently, manure and sludge pre-application treatments generally reduce but do not eliminate ARB and ARGs, so that spreading treated manures and sludges may still represent a potential risk of contamination of adjacent water resources through runoff or soil leaching.

5.5. Wildlife as a reservoir for ARB and ARGs


Wildlife, mainly birds, mammals but also invertebrates, are suspected to be involved in the spread of ARB in the environment. ARB and ARGs have been detected in the intestinal microbiota of terrestrial vertebrates (e.g. wild boars, wolves, rodents) with omnivorous or carnivorous animals being more often contaminated with ARB than herbivores (Vittecoq et al., 2016). In the freshwater environment, fish feeding on periphyton close to WWTP discharges were contaminated with ESBL-producing *E. coli* (Bollache et al., 2019). Finally, birds have been repeatedly described as ESBL carriers, and the frequency of ARB carriage by seabirds increases with proximity to humans (Bonnedahl et al., 2009; Haenni et al., 2020; Vittecoq et al., 2017). Moreover, antimicrobial contamination of migratory birds raises further questions on the capacity of these animals to disseminate ARB and ARGs over very long distances. Globally, almost all of these studies showed that the occurrence of ARB in aquatic or terrestrial wildlife is reflecting both the diet of the wildlife and the impact of human activities (Ramey and Ahlstrom, 2020).

6. Potential (co)selection of antimicrobial resistance in the environment in France

6.1. Do antibiotic concentrations in treated wastewater and receiving bodies favor antibiotic resistance dissemination?

In order to assess the risk of antibiotics to select for or to favor the persistence of AMR in French waters, we compared antibiotic concentrations quantified in treated wastewater, receiving water, and groundwater with PNEC values (Fig. 7). Murray et al. (Murray et al., 2021) gave PNEC-R (PNEC for resistance) and PNEC-P (PNEC for persistence) based on experimental data with mixed bacterial communities. Experimental data were available for eleven antibiotics (cefotaxime, azithromycin, clarithromycin, erythromycin, ciprofloxacin, chloramphenicol, gentamicin, kanamycin, streptomycin, tetracycline, and trimethoprim) which span seven antibiotic classes. We had robust data (with MECs being assessed > 10 times) for all these compounds,

A



B




Fig. 7. Antibiotic concentrations in the dissolved phase of various liquid environmental matrices (antibiotic alone in light gray; sum of all antibiotic residues from the same class in dashed grey) and the predicted no effect concentration for resistance (PNEC-R) and for persistence (PNEC-P) (dark gray) for ciprofloxacin (panel A), trimethoprim (panel B), macrolides (panel C) and tetracycline (panel D). FQ, fluoroquinolones; TMP, trimethoprim; ML, macrolides; TC, tetracyclines; N, number of samples; PNEC values were taken from (Murray et al., 2021). The PNEC values were those of ciprofloxacin (panel A; PNEC-R, 50–780 ng.L^{-1} ; PNEC-P, 10 ng.L^{-1}), trimethoprim (panel B; PNEC-R, 1,560–3,130 ng.L^{-1} ; PNEC-P, 1,000 ng.L^{-1}), azithromycin, clarithromycin (panel C; PNEC-R, 50,000–12,500,000 ng.L^{-1} ; no PNEC-P yet defined), tetracycline (panel D; no PNEC-R yet defined; PNEC-P: 10 ng.L^{-1}).

except aminoglycosides for environmental liquid matrices in France (see Supplemental Table 1). Of note, cefotaxime and chloramphenicol were detected in $\leq 3\%$ of the tested surface water. PNECs were still unknown for penicillins, carbapenems, sulfonamides, and colistin (Murray et al., 2021).

Only concentrations in the dissolved phases of the liquid matrices of treated wastewater, surface water and groundwater were considered because of strong uncertainties in concentrations and bioavailability in other environmental matrices. For example, concentrations reported on a dry weight basis in matrices that have high moisture contents such as

periphyton or sediments will be an overestimation of the concentration that microorganisms are exposed to (Jonker, 2021). Likewise, the bioavailability of antibiotics in complex matrices such as soils and sediments will be constrained by sorptive processes that will vary widely with the antibiotic and the physical and chemical composition of the matrix (Al-Khazrajy et al., 2018; Li et al., 2021).

Considering that antibiotics of the same class can induce a biological response at similar concentrations, we used the individual antibiotic concentrations and the sum of the concentrations of antibiotics of the same class to consider a potential additive effect.




Fig. 7. (continued).

The ciprofloxacin concentrations in treated wastewater and in the most polluted surface water could favor the emergence of resistance. The PNEC-P of ciprofloxacin (10 ng.L^{-1}) was low enough to be reached in all the liquid matrices tested (Fig. 7A). In contrast, the cumulated concentrations of macrolides and the concentration of trimethoprim did not reach their respective PNECs (Fig. 7B and 7C). The concentrations of tetracycline in treated wastewater and in surface water reached the PNEC-P of the compound (10 ng.L^{-1}) (Fig. 7D). Fig. 8 displays the risk quotients (RQs) for aquatic environments in France calculated from PNEC-R and MECs. Overall, the antibiotic likely to pose the greatest risk to the French environment is ciprofloxacin, and by extension all fluoroquinolones. These observations are in agreement with those derived from international data on fluoroquinolone MECs (Chow et al., 2021). However, the application of *in vitro* results to predict effects that the

fluoroquinolone MECs may exert (Fig. 7A) must be tempered by the potential bioaccessibility and bioavailability of residues *in situ* (see Section 3.3). Although trimethoprim concentration does not reach the PNEC, this antibiotic is at medium risk in the most polluted wastewater and receiving rivers.

6.2. Associations between environmental concentrations of selective agents and antimicrobial resistance

Knowledge about the impact of selective agents on antibiotic resistance in the environment is still patchy. However, based on studies carried out *in situ* and the analysis of the information outlined above, some conclusions can be drawn.

An environment contaminated by bacteria resistant to a certain class




Fig. 8. Risk quotients (RQs) for aquatic environments (treated wastewater and surface water) in France. RQ_{max} (RQ maximum) and RQ_{med} (RQ median) were based on maximum and median measured environmental concentrations (MECs) divided by the PNEC-R determined experimentally with the SELECT method (Murray et al., 2020). MECs were extracted from Supplemental Table 1. RQs were represented on a logarithmic scale. High, medium, and low risks were defined by Log₁₀ RQ values > 0, -1 to 0, and < -1, respectively. We kept for analysis antibiotics whose MEC was assessed > 10 times and which were above the detection limit in > 10 % of the cases.

of antibiotics, for example β -lactams, may not contain antibiotics in that class if the antibiotics are not inherently persistent. For instance, the presence of penicillin-resistant *E. coli* in a river in which penicillins were undetectable suggests that resistance was acquired in the digestive tract of individuals (human and/or animal) receiving antibiotics and not in the environment (Oberlé et al., 2012; Petit et al., 2012). Sampling multiple sites upstream and downstream of the wastewater treatment plant in the Vienne catchment area (Rhône river) failed to reveal associations between antibiotic concentrations in river periphytons and the abundance of *intI1* (Aubertheau-Laurent, 2013; Aubertheau et al., 2017). This is in line with non-French studies showing that, with the exception of pharmaceutical industry discharges, the abundance of ARGs in aquatic environments seems due to fecal contamination by ARB rather than selection of resistant environmental bacteria (Ahmed et al., 2018; Karkman et al., 2019; Milaković et al., 2019).

Terrestrial or aquatic environments are potentially contaminated by mixtures of selective agents, among which heavy metal and biocides can contribute to the maintenance of AMR in the environment by exerting a co-selection pressure (see Section 3.1) (Pal et al., 2017). However, there is little data available to indicate if this happens *in situ* (Berg et al., 2010; Carey and McNamara, 2014; Han et al., 2019; Middleton and Salierno, 2013; Tandukar et al., 2013; Zhao et al., 2019), and the effects (synergistic, additive, or antagonistic effects between different compounds) of mixtures is difficult to anticipate (Gullberg et al., 2014; Vos et al., 2020). Although it is reasonable to speculate that different antibiotic classes targeting the same bacterial component (*i.e.* macrolides and tetracyclines) would be additive in mixtures, there are no data in the literature on this subject.

7. Perspectives and recommendations

This review revealed numerous knowledge gaps and limitations in the comparison and generalization of the available data for the context of France. We faced several difficulties including the absence or paucity of data for several sources, the overall lack of metadata and the lack of coherent and comparable sampling strategies in time and space. To compensate for a lack of French data, environmental contamination measured in countries sharing socio-geographic characteristics similar to France, *i.e.* Europe and Canada, was used for comparison. Likewise, conclusions of this review are applicable to countries that share similar attributes; the more variance from these characteristics, the less applicable the analysis will be. We thus recommend six main avenues to globally improve and broaden information on the burden of AMR in the environment.

7.1. Harmonization of sampling, methods and indicators

In contrast to ARB and ARGs, databases already exist concerning the monitoring of environmental contamination by antibiotics (see Appendix B). However, comparisons between studies are difficult, due to the diversity of the measured parameters. Likewise, sampling and analytical methods need harmonization for all chemical and microbial contaminants of water resources. We thus recommend:

- to optimize and sustain data acquisition by providing a minimal list of common indicators (ARB and ARGs) required to monitor environmental contamination (Table 1). These indicators, chosen based on current knowledge and available analytical methods, will allow a spatial and temporal comparison of the environmental contamination dynamics between studies, but also in the different environmental compartments. Such a minimal list of common indicators was initiated by the WHO, who proposed a simple and broadly implementable protocol (called “Tricycle”) to detect ESBL-producing *E. coli* in the three human, animal and environmental sectors (WHO, 2021).
- to define priority antibiotics to be monitored in the aquatic environment. Where available, validated analytical methods that comply with national and/or international standards must be used to facilitate inter-study comparisons. In France, we propose to monitor representatives of five antibiotic classes: fluoroquinolones (ciprofloxacin), trimethoprim, sulfonamides (sulfamethoxazole, sulfamethazine), tetracyclines (tetracycline), and aminoglycosides (gentamicin). Compounds which have a low RQ (*e.g.* macrolides), limited usage (*e.g.* chloramphenicol, colistin), and those that are rapidly dissipated in the environment (*e.g.* β -lactams) will be excluded.
- to monitor the resistance patterns of ubiquitous pathogenic bacterial species able to live in the environment and humans (*e.g.* *Klebsiella pneumoniae*, *Stenotrophomonas maltophilia*, *Aeromonas hydrophila*).
- to monitor the spatial and temporal dissemination of antibiotics, ARB and ARGs in distinct receiving environments, and to evaluate the variability over time of these contaminant concentrations in receiving waters in study-sites and/or instrumented sites representative of the geographic diversity and land use of the French and European territory. Ideally, studies should cover the parameters listed above (antibiotics, ARB, ARG) for WWTP effluents, receiving surface water > 1 km downstream of the effluent pipe, and groundwater (comprehensive sampling). In smaller-scale studies, the number of samples might first be reduced to receiving surface water

Table 1
Proposed indicators of antimicrobial resistance in the environment.

Proposed indicator	Method	Results and units	Advantages	Limitations
<i>E. coli</i> resistant to 3rd generation cephalosporins or ESBL-producing <i>E. coli</i> ^a	Culture on selective media	<ul style="list-style-type: none"> – Absolute value (CFU.L⁻¹ or CFU.g⁻¹) preferable – Relative value (relative to abundance of total <i>E. coli</i>) 	<ul style="list-style-type: none"> – Relatively simple tracking – Indicators of environmental exposure – Present in soils, water, sediments – Assess the anthropogenic impact on AMR in the environment – Identify hotspots and/or periods at risk of fecal contamination – Indicators shared by human and veterinary practices – Indicator proposed by the WHO Tricycle protocol 	<ul style="list-style-type: none"> – Do not allow the description of new ARB – Quickly lose their cultivability in the environment
<i>int1</i> ^b	qPCR	<ul style="list-style-type: none"> – Relative abundance (gene copy / 16S rRNA) – Number of copies.L⁻¹ for liquid matrices – Number of copies.g⁻¹ DM⁻¹ for solid matrices 	<ul style="list-style-type: none"> – Relatively simple tracking – Indicators of anthropogenic pressure – Can be coupled with the ARG search to evaluate their mobility 	<ul style="list-style-type: none"> – Does not identify ARGs present in the matrices – Method partially standardized – Possible problem of extraction and/or amplification inhibitors in some contaminated environmental matrices – Limit of quantification ~ 10³ gene copies – Since <i>int1</i> is widespread, there is a need of “blank” data on pristine environments in order to infer trends in <i>int1</i> abundance.

^a These two parameters partially overlap. Currently, resistance to 3rd generation cephalosporins in *E. coli* is predominantly mediated by ESBL production.

^b Future recommendations for qPCR targets will be based on the outcomes of metagenomic surveys of municipal and agricultural effluents.

with all parameters tested (intermediate sampling). Ultimately, parameters might be restricted to the quantification of *E. coli* and ESBL-producing *E. coli* in receiving surface water (limited sampling).

7.2. Placing the One Health concept on a global scale

We recommend the creation of a long-term integrated surveillance network using a One Health approach, which connects ARB, ARGs, and antibiotic residues data from environmental, human, and animal compartments. Each surveillance system must take into account the distribution of the different farming types over the territory to prioritize regions with the highest risk of contamination. We also recommend open centralized repositories for surveillance data and metadata at the national and European levels. The success of a national surveillance initiative requires the use of internal controls and standardized techniques. However, such guidelines are still lacking nationally and internationally for the indicators proposed in Table 1. Laboratories must then use procedures guaranteeing the quality and comparability of the associated data and metadata. Moreover, a reconciliation of the various regulatory monitoring tools (environmental and sanitary) would facilitate the management of AMR in the environment. The four antibiotics (amoxicillin, ciprofloxacin, trimethoprim, and sulfamethoxazole) on the 3rd version of the Water Framework Directive’s Watch List (Gomez Cortes et al., 2020) included the one that is likely to pose the greatest risk to the French environment (*i.e.* ciprofloxacin). However, ciprofloxacin only represents ~ 30% of the prescription of fluoroquinolones in France (Santé Publique France, 2017). Since, the PNECs of other major fluoroquinolones (*i.e.* levofloxacin and ofloxacin) are likely similar to those of ciprofloxacin, the next Watch List should also include these compounds.

In the future, these recommendations should be adapted based on the epidemiology of ARB and ARGs in human and animals, and on the development of new methods. Applications of metagenomics in surveillance of wastewater effluents and agricultural effluents is an example of evolving approaches that hold promise.

7.3. Broaden the panel of matrices and sources tested

In the French context, it is necessary to increase the range of matrices studied notably to consider the particulate fraction of liquid matrices, sediments and the periphyton. Monitoring of contamination levels

should be extended to other potential sources and receiving matrices. Sources of contamination for which data are sorely needed include sewerage, installations producing or formulating antibiotics, and old landfill sites. Receiving bodies for which there is very little information include fish farms, coastal waters, soils from terrestrial environments such as urban, *peri*-urban and agroforestry and polluted sites, and soil meso- and macrofauna such as earthworms and arthropods which can both constitute hotspots and play a role of dissemination vectors.

7.4. Anticipate climate change impacts on AMR in the environment

Climate change in Europe is likely to modify the environmental contamination with AMR and antibiotics. In the near future, the expected increase in the frequency of extreme rainfall events (EASAC, 2018), and the expected sharp variation of river flows will increase the risk of contamination by ARB, ARGs, and antibiotics. Hence, both the combined sewer overflows and the resuspension of sediments during extreme rainfall events can enhance the release of antibiotics, ARB, and ARG into the aquatic compartment (Olds et al., 2018; Pérez-Valdespino et al., 2021). Finally, lower minimum flows imply less volume for dilution and, hence, higher concentrations downstream of point discharges such as WWTP.

7.5. Clarify the impact of antibiotics on the development of antimicrobial resistance and its dissemination

There is a need to determine the sub-inhibitory concentrations of antibiotics, on their own and in mixtures, that favor the persistence, dissemination, selection and the emergence of AMR through *in vitro* experimentation in complex media or through experiments at different scales (*e.g.* at the laboratory with biofilms and mesocosms, or *in situ* with field plots). Likewise, it is necessary to identify the environmental conditions allowing the persistence and dissemination of AMR and to study the expression of panel of ARGs under anthropogenic pressure. The determination of PNEC-R and/or PNEC-P values for highly-prescribed antibiotics (tetracyclines, sulfonamides, azoles) using experimental approaches with bacterial community should be a priority (Murray et al., 2021).

7.6. Change the scale to study interactions between antibiotics and antibiotic resistance

We must also increase our knowledge on the actual exposure of bacterial communities to antibiotics, by a better characterization of the bioavailability at a microenvironment scale considering the interactions between bacterial populations and all the constituents of its environment. Hence, the impact of anthropogenic activities on environmental microbial communities is generally assessed on a macroscopic scale. However, the environment in which microorganisms live, given their size, is at the μm scale (Nunan et al., 2001; Ranjard and Richaume, 2001). The concepts of microbial ecology and of microbial ecotoxicology have not been sufficiently taken into account for the study of AMR, particularly on the scale of these microenvironments (Banerji et al., 2019).

The impact of selective agents in the environment has mainly been studied in liquid matrices. In solid matrices, the bioavailability and bioaccessibility of antibiotics remain difficult to quantify (Menz et al., 2018; Sidhu et al., 2019). Studies on antibiotics in soils are mostly carried out using destructive approaches by homogenizing samples. This neglects the notions of microbial habitats and likely gives biased views on the exposure levels of soil aggregates.

At a macroscopic scale, the development of digital big data processing tools (e.g. machine learning and deep learning based on artificial intelligence) could analyze environmental monitoring data to assess the risk of AMR retention in different situations. New numerical prediction tools that could anticipate potential evolutions (climate change, changes of water use) could help policy-makers (Doorn, 2021).

7.7. Plan and act using a 'one health' approach

Taking all the above recommendations into consideration, the "One Health" approach will necessarily be multidisciplinary and will bring together microbiologists of all backgrounds (basic science, environmental or clinical microbiology), veterinarians, physicians, pharmacists, chemists, but also mathematicians, computer scientists, big data analysts, and specialists in the social sciences. Their results would orient research and investment priorities to reduce environmental contamination with AMR. The importance of global transfers of goods, animals and people reminds us that AMR does not stop at borders. It is therefore fundamental to consider AMR on a global scale.

Appendix A. List of acronyms

AMR	Antimicrobial resistance
ARB	Antimicrobial-resistant bacteria commensal or pathogenic for humans
ARG	Antibiotic resistance genes and associated genes (e.g. <i>intI</i>)
DM	Dry matter
LOD	Limit of detection
MIC	Minimum inhibitory concentration
MSC	Minimal selective concentration
OWP	Organic waste product
PE	Population equivalent
PNEC-P	Predicted no effect concentration for persistence
PNEC-R	Predicted no effect concentration for resistance
VBNC	viable but non-culturable
WHO	World Health Organization
WWTP	Wastewater treatment plant

Appendix B List of databases

Name	Description	Web site
PIREN	Database on the hydrographic network of the Seine river	piren-seine.fr
SOKARST	Network of karst groundwater monitors	sokarst.org
ADES	Groundwater database	ades.eaufrance.fr
NAIADES	Continental water database	naiaades.eaufrance.fr

(continued on next page)

Funding

This assessment was conducted by the ad hoc working group "Antimicrobial resistance and the environment" of the French Agency for Food, Environmental and Occupational Health & Safety (ANSES).

CRediT authorship contribution statement

Marisa Haenni: Investigation, Writing – review & editing. **Christophe Dagot:** Investigation, Writing – original draft. **Olivier Chesneau:** Investigation, Writing – review & editing. **Delphine Bibbal:** Investigation, Writing – original draft. **Jérôme Labanowski:** Investigation, Writing – review & editing. **Michèle Vialette:** Investigation. **Damien Bouchard:** Investigation, Writing – original draft. **Fabrice Martin-Laurent:** Investigation, Writing – original draft. **Louisiane Calsat:** Investigation, Data curation, Writing – original draft. **Sylvie Nazaret:** Investigation, Writing – original draft. **Fabienne Petit:** Investigation, Writing – review & editing. **Anne-Marie Pourcher:** Investigation, Writing – original draft. **Anne Togola:** Investigation, Data curation, Writing – original draft. **Morgane Bachelot:** Investigation, Supervision. **Edward Topp:** Investigation, Writing – review & editing. **Didier Hocquet:** Investigation, Supervision, Writing – review & editing.

Declaration of Competing Interest

The authors declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Acknowledgements

This document was prepared thanks to the collective expert assessment, carried out by the Anses expert working group 'Antimicrobial resistance and the environment' (ANSES opinion 2016-SA-0252), chaired by Morgane Bachelot and whose active contributors are co-authors of this publication.

We thank all members of the ANSES committee of specialized experts on water (CES eaux; President Gilles Bornert) for helpful discussions. We also thank Jean-Yves Madec, Johnny Gasperi and Laurent Moulin for their thorough proofreading.

(continued)

Name	Description	Web site
QUADRIGE	Coastal water database	quadrige.eaufrance.fr
SIPIBEL	Surface water, groundwater, wastewater database	graie.org/sipibel
METEOFRANCE	French weather database	meteofrance.com

Appendix C. Supplementary material

Supplementary data to this article can be found online at <https://doi.org/10.1016/j.envint.2021.107047>.

References

- Ademe, 2018. Matières fertilisantes organiques: gestion et épandage. Guide des bonnes pratiques. 15p.
- Ahmed, W., Lobos, A., Senkbeil, J., Peraud, J., Gallard, J., Harwood, V.J., 2018. Evaluation of the novel crAssphage marker for sewage pollution tracking in storm drain outfalls in Tampa, Florida. *Water Res.* 131, 142–150.
- Al-Khazrajy, O.S.A., Bergström, E., Boxall, A.B.A., 2018. Factors affecting the dissipation of pharmaceuticals in freshwater sediments. *Environ. Toxicol. Chem.* 37, 829–838.
- Algros, E., Jourdain, M.-J., 2007. Contamination potentielle des échantillons de stations d'épuration (eaux brutes, eaux traitées, boues) et effluents d'élevage par des molécules pharmaceutiques à usage humain et vétérinaire. *IRH Environ.*
- Alygizakis, N.A., Gago-Ferrero, P., Borova, V.L., Pavlidou, A., Hatzianestis, I., Thomaidis, N.S., 2016. Occurrence and spatial distribution of 158 pharmaceuticals, drugs of abuse and related metabolites in offshore seawater. *Sci. Total Environ.* 541, 1097–1105.
- Andersson, D.I., Hughes, D., 2014. Microbiological effects of sublethal levels of antibiotics. *Nat. Rev. Microbiol.* 12, 465.
- Anses, 2020a. Antibiorésistance et environnement. État et causes possibles de la contamination des milieux en France (saisine n°2016-SA-0252). Agence nationale de sécurité sanitaire de l'alimentation, de l'environnement et du travail. (Maisons-Alfort).
- Anses, 2020b. Suivi des ventes de médicaments vétérinaires contenant des antibiotiques en France en 2019 (Fougères, France, Agence nationale de sécurité sanitaire de l'alimentation, de l'environnement et du travail - Agence nationale du médicament vétérinaire), 108.
- Arias-Andres, M., Klümper, U., Rojas-Jimenez, K., Grossart, H.-P., 2018. Microplastic pollution increases gene exchange in aquatic ecosystems. *Environ. Pollut.* 237, 253–261.
- Arias-Andres, M., Rojas-Jimenez, K., Grossart, H.-P., 2019. Collateral effects of microplastic pollution on aquatic microorganisms: An ecological perspective. *TrAC, Trends Anal. Chem.* 112, 234–240.
- Aubertheau-Laurent, E., 2013. Évaluation de l'état de contamination des bassins versants par les résidus de médicaments : utilisation des biofilms épithéliques comme marqueur d'imprégnation du milieu. Université de Poitiers.
- Aubertheau, E., Stalder, T., Mondamert, L., Ploy, M.-C., Dagot, C., Labanowski, J., 2017. Impact of wastewater treatment plant discharge on the contamination of river biofilms by pharmaceuticals and antibiotic resistance. *Sci. Total Environ.* 579, 1387–1398.
- Ayrapetyan, M., Williams, T., Oliver, J.D., 2018. Relationship between the viable but nonculturable state and antibiotic persister cells. *J. Bacteriol.* 200, e00249–00218.
- Azimi, S., Guérin, S., Garcia-Gonzalez, E., Candido, P., Couturier, G., Joyeux, M., Lavison, G., Rocher, V., 2018. Pharmaceuticals in Seine water and wastewater treatment plant outfalls: the Paris conurbation case. *Techniques Sci. Méthodes* 6, 45–58.
- Baharoglu, Z., Mazel, D., 2011. *Vibrio cholerae* triggers SOS and mutagenesis in response to a wide range of antibiotics: A route towards multiresistance. *Antimicrob. Agents Chemother.* 55, 2438–2441.
- Baharoglu, Z., Mazel, D., 2014. SOS, the formidable strategy of bacteria against aggressions. *FEMS Microbiol. Rev.* 38, 1126–1145.
- Baker, D.R., Kasprzyk-Hordern, B., 2013. Spatial and temporal occurrence of pharmaceuticals and illicit drugs in the aqueous environment and during wastewater treatment: New developments. *Sci. Total Environ.* 454–455, 442–456.
- Balcázar, J.L., Subirats, J., Borrego, C.M., 2015. The role of biofilms as environmental reservoirs of antibiotic resistance. *Front. Microbiol.* 6, 1216–1216.
- Banerji, A., Jahne, M., Herrmann, M., Brinkman, N., Keely, S., 2019. Bringing community ecology to bear on the issue of antimicrobial resistance. *Front. Microbiol.* 10.
- Barrios, R.E., Khuntia, H.K., Bartelt-Hunt, S.L., Gilley, J.E., Schmidt, A.M., Snow, D.D., Li, X., 2020. Fate and transport of antibiotics and antibiotic resistance genes in runoff and soil as affected by the timing of swine manure slurry application. *Sci. Total Environ.* 712, 136505.
- Batt, A.L., Bruce, I.B., Aga, D.S., 2006. Evaluating the vulnerability of surface waters to antibiotic contamination from varying wastewater treatment plant discharges. *Environ. Pollut.* 142(2), pp. 295–302.
- Berendonk, T.U., Manaia, C.M., Merlin, C., Fatta-Kassinos, D., Cytryn, E., Walsh, F., Bürgmann, H., Sørum, H., Norström, M., Pons, M.-N., Kreuzinger, N., Huovinen, P., Stefani, S., Schwartz, T., Kisand, V., Baquero, F., Martinez, J.L., 2015. Tackling antibiotic resistance: The environmental framework. *Nat. Rev. Microbiol.* 13, 310.
- Berg, J., Thorsen, M.K., Holm, P.E., Jensen, J., Nybroe, O., Brandt, K.K., 2010. Cu exposure under field conditions coselects for antibiotic resistance as determined by a novel cultivation-independent bacterial community tolerance assay. *Environ. Sci. Technol.* 44, 8724–8728.
- Berthe, T., Ratajczak, M., Clermont, O., Denamur, E., Petit, F., 2013. Evidence for coexistence of distinct *Escherichia coli* populations in various aquatic environments and their survival in estuary water. *Appl. Environ. Microbiol.* 79, 4684–4693.
- Bibbal, D., Kérouredan, M., Loukiadis, E., Scheutz, F., Oswald, E., Brugère, H., 2014. Slaughterhouse effluent discharges into rivers not responsible for environmental occurrence of enteroaggregative *Escherichia coli*. *Vet. Microbiol.* 168, 451–454.
- Bollache, L., Bardet, E., Depret, G., Motreuil, S., Neuwirth, C., Moreau, J., Hartmann, A., 2019. Dissemination of CTX-M-producing *Escherichia coli* in freshwater fishes from a French watershed (Burgundy). *Front. Microbiol.* 9.
- Bonnedahl, J., Drobní, M., Gauthier-Clerc, M., Hernandez, J., Granholm, S., Kayser, Y., Melhus, A., Kahlmeter, G., Waldenström, J., Johansson, A., Olsen, B., 2009. Dissemination of *Escherichia coli* with CTX-M type ESBL between humans and yellow-legged gulls in the south of France. *PLoS ONE* 4, e5958.
- Bonnet, R., 2004. Growing group of extended-spectrum beta-lactamases: the CTX-M enzymes. *Antimicrob. Agents Chemother.* 48, 1–14.
- Bourdat-Deschamps, M., Ferhi, S., Bernet, N., Feder, F., Crouzet, O., Patureau, D., Montenach, D., Moussard, G.D., Mercier, V., Benoit, P., Houot, S., 2017. Fate and impacts of pharmaceuticals and personal care products after repeated applications of organic waste products in long-term field experiments. *Sci. Total Environ.* 607–608, 271–280.
- Boxall, A.B., Fogg, L.A., Blackwell, P.A., Kay, P., Pemberton, E.J., Croxford, A., 2004. Veterinary medicines in the environment. *Rev. Environ. Contam. Toxicol.* 180, 1–91.
- Bréchet, C., Plantin, J., Sauget, M., Thouvez, M., Talon, D., Chollet, P., Guyeux, C., Hocquet, D., Bertrand, X., 2014. Wastewater treatment plants release large amounts of extended-spectrum β -lactamase-producing *Escherichia coli* into the environment. *Clin. Infect. Dis.* 58, 1658–1665.
- Buelow, E., Bayjanov, J.R., Majoor, E., Willems, R.J., Bonten, M.J., Schmitt, H., van Schaik, W., 2018. Limited influence of hospital wastewater on the microbiome and resistome of wastewater in a community sewerage system. *FEMS Microbiol. Ecol.* 94.
- Buelow, E., Rico, A., Gaschet, M., Lourenço, J., Kennedy, S.P., Wiest, L., Ploy, M.-C., Dagot, C., 2020. Hospital discharges in urban sanitation systems: Long-term monitoring of wastewater resistome and microbiota in relationship to their eco-exposure. *Water Res.* X 7, 100045.
- Camilleri, J., Baudot, R., Wiest, L., Vulliet, E., Cren-Olivé, C., Daniele, G., 2015. Multiresidue fully automated online SPE-HPLC-MS/MS method for the quantification of endocrine-disrupting and pharmaceutical compounds at trace level in surface water. *Int. J. Environ. Anal. Chem.* 95, 67–81.
- Cantas, L., Shah, S., Cavaco, L., Manaia, C., Walsh, F., Popowska, M., Garelick, H., Bürgmann, H., Sørum, H., 2013. A brief multi-disciplinary review on antimicrobial resistance in medicine and its linkage to the global environmental microbiota. *Front. Microbiol.* 4.
- Capdeville, M.-J., 2011. Études des cycles biogéochimiques des contaminants organiques dits "émergents" dans les systèmes aquatiques. Université de Bordeaux 1.
- Carey, D.E., McNamara, P.J., 2014. The impact of triclosan on the spread of antibiotic resistance in the environment. *Front. Microbiol.* 5.
- Cassini, A., Högberg, L.D., Plachouras, D., Quattrocchi, A., Hoxha, A., Simonsen, G.S., Colomb-Cotinat, M., Kretzschmar, M.E., Devleeschauwer, B., Cecchini, M., Ouakrim, D.A., Oliveira, T.C., Struelens, M.J., Suetens, C., Monnet, D.L., Strauss, R., Mertens, K., Struyf, T., Catry, B., Latour, K., Ivanov, I.N., Dobrev, E.G., Tambic Andrasevic, A., Soprek, S., Budimir, A., Paphitov, N., Zemlicková, H., Schyette Olsen, S., Wolff Sönksen, U., Märtin, P., Ivanova, M., Lyytikäinen, O., Jalava, J., Coignard, B., Eckmanns, T., Abu Sin, M., Haller, S., Daikos, G.L., Gikas, A., Tsiodras, S., Kontopidou, F., Tóth, Á., Hajdu, Á., Guólaugsson, Ó., Kristinsson, K.G., Murchan, S., Burns, K., Pezzotti, P., Gagliotti, C., Dumpis, U., Liiumiemi, A., Perrin, M., Borg, M.A., de Greeff, S.C., Monen, J.C.M., Koek, M.B.G., Elström, P., Zabicka, D., Deptula, A., Hryniewicz, W., Caniça, M., Nogueira, P.J., Fernandes, P.A., Manogovic, V., Popescu, G.A., Serban, R.I., Schréterová, E., Litvová, S., Štefkovicová, M., Kolman, J., Klavs, I., Korošec, A., Aracil, B., Asensio, A., Pérez-Vázquez, M., Billström, H., Larsson, S., Reilly, J.S., Johnson, A., Hopkins, S., 2019. Attributable deaths and disability-adjusted life-years caused by infections with antibiotic-resistant bacteria in the EU and the European Economic Area in 2015: A population-level modelling analysis. *Lancet Infect. Dis.* 19, 56–66.
- ChangingMarkets, 2016. Superbugs in the Supply Chain: how pollution from antibiotics factories in India and China is fuelling the global rise of drug-resistant infections. <http://www.changingmarkets.org>

- ps://epha.org/wp-content/uploads/2016/10/Superbugsinthesupplychain_CMR_eport.pdf.
- Charuaud, L., Jardé, E., Jaffrézic, A., Liotaud, M., Goyat, Q., Mercier, F., Le Bot, B., 2019. Veterinary pharmaceutical residues in water resources and tap water in an intensive husbandry area in France. *Sci. Total Environ.* 664, 605–615.
- Chen, Z., Zhang, Y., Gao, Y., Boyd, S.A., Zhu, D., Li, H., 2015. Influence of dissolved organic matter on tetracycline bioavailability to an antibiotic-resistant bacterium. *Environ. Sci. Technol.* 49, 10903–10910.
- Chonova, T., Keck, F., Labanowski, J., Montuelle, B., Rimet, F., Bouchez, A., 2016. Separate treatment of hospital and urban wastewaters: A real scale comparison of effluents and their effect on microbial communities. *Sci. Total Environ.* 542, 965–975.
- Chonova, T., Labanowski, J., Cournoyer, B., Chardon, C., Keck, F., Laurent, E., Mondamert, L., Vasselon, V., Wiest, L., Bouchez, A., 2018. River biofilm community changes related to pharmaceutical loads emitted by a wastewater treatment plant. *Environ. Sci. Pollut. Res.* 25, 9254–9264.
- Chow, L.K.M., Ghaly, T.M., Gillings, M.R., 2021. A survey of sub-inhibitory concentrations of antibiotics in the environment. *J. Environ. Sci.* 99, 21–27.
- Coetsier, C.M., Spinelli, S., Lin, L., Roig, B., Touraud, E., 2009. Discharge of pharmaceutical products (PPs) through a conventional biological sewage treatment plant: MECs vs PECs? *Environ. Int.* 35, 787–792.
- Collignon, P., Beggs, J.J., Walsh, T.R., Gandra, S., Laxminarayan, R., 2018. Anthropological and socioeconomic factors contributing to global antimicrobial resistance: A univariate and multivariable analysis. *The Lancet Planet. Health* 2, e398–e405.
- Comité interministériel pour la santé, 2016. Feuille de route interministérielle de maîtrise de l'antibiorésistance, 100.
- Commissariat général au développement durable, 2019. Rapport de synthèse, L'environnement en France.
- Dinh, Q.T., Moreau-Guigon, E., Labadie, P., Alliot, F., Teil, M.J., Blanchard, M., Eurin, J., Chevreuil, M., 2017a. Fate of antibiotics from hospital and domestic sources in a sewage network. *Sci. Total Environ.* 575, 758–766.
- Dinh, Q.T., Nguyen, T.A., Moreau-Guigon, E., Alliot, F., Teil, M.-J., Blanchard, M., Chevreuil, M., 2017b. Trace-level determination of oxolinic acid and flumequine in soil, river bed sediment, and river water using microwave-assisted extraction and high-performance liquid chromatography with fluorimetric detection. *Soil Sediment Contamination: Int. J.* 26, 247–258.
- Doom, N., 2021. Artificial intelligence in the water domain: Opportunities for responsible use. *Sci. Total Environ.* 755, 142561.
- Drieux, L., Haenni, S., Moulin, L., Jarlier, V., 2016. Quantitative evaluation of extended-spectrum β -lactamase-producing *Escherichia coli* strains in the wastewater of a French teaching hospital and relation to patient strain. *Antimicrobial Resistance Infection Control* 5, 9.
- EASAC, 2018. Extreme weather events in Europe - Preparing for climate change adaptation: an update on EASAC's 2013 study (Halle, Allemagne, European Academies Science Advisory Council).
- ECDC. Antimicrobial consumption database (ESAC-Net). <https://www.ecdc.europa.eu/en> (last accessed 24/09/2021).
- European Commission, 2017. A European One Health Action Plan against Antimicrobial Resistance (AMR).
- European Commission, 2019. Strategic approach to pharmaceuticals in the environment. Fairbairn, D.J., Karpuzcu, M.E., Arnold, W.A., Barber, B.L., Kaufenberg, E.F., Koskinen, W.C., Novak, P.J., Rice, P.J., Swackhamer, D.L., 2016. Sources and transport of contaminants of emerging concern: A two-year study of occurrence and spatiotemporal variation in a mixed land use watershed. *Sci. Total Environ.* 551–552, 605–613.
- Feitos-Felizzola, J., Chiron, S., 2009. Occurrence and distribution of selected antibiotics in a small Mediterranean stream (Arc River, Southern France). *J. Hydrol.* 364, 50–57.
- Fisher, R.A., Gollan, B., Helaine, S., 2017. Persistent bacterial infections and persister cells. *Nat. Rev. Microbiol.* 15, 453–464.
- Flemming, H.-C., Wingender, J., 2010. The biofilm matrix. *Nat. Rev. Microbiol.* 8, 623–633.
- Flemming, H.C., Wingender, J., Szewzyk, U., Steinberg, P., Rice, S.A., Kjelleberg, S., 2016. Biofilms: an emergent form of bacterial life. *Nat. Rev. Microbiol.* 14, 563–575.
- Furuya, E.Y., Lowy, F.D., 2006. Antimicrobial-resistant bacteria in the community setting. *Nat. Rev. Microbiol.* 4, 36–45.
- Galvin, S., Boyle, F., Hickey, P., Vellinga, A., Morris, D., Cormican, M., 2010. Enumeration and characterization of antimicrobial-resistant *Escherichia coli* bacteria in effluent from municipal, hospital, and secondary treatment facility sources. *Appl. Environ. Microbiol.* 76, 4772–4779.
- García-Armisen, T., Anzil, A., Cornelis, P., Chevreuil, M., Servais, P., 2013. Identification of antimicrobial resistant bacteria in rivers: Insights into the cultivation bias. *Water Res.* 47, 4938–4947.
- Gomez Cortes, L., Marinov, D., Sanseverino, I., Navarro Cuenca, A., Niegowska, M., Porcel Roderiguez, E., Lettieri, T., 2020. Selection of Substances For the 3rd Watch List Under the Water Framework Directive. Publications Office of the European Union, Luxembourg, p. 2020.
- Gordon, L., Giraud, E., Ganière, J.P., Armand, F., Bouju-Albert, A., De La Cotte, N., Mangion, C., Le Bris, H., 2007. Antimicrobial resistance survey in a river receiving effluents from freshwater fish farms. *J. Appl. Microbiol.* 102, 1167–1176.
- Goulas, A., Belhadi, D., Descamps, A., Andremont, A., Benoit, P., Courtois, S., Dagot, C., Grall, N., Makowski, D., Nazaret, S., Nélieu, S., Patureau, D., Petit, F., Roose-Amsaleg, C., Vittecoq, M., Livoreil, B., Laouénan, C., 2020. How effective are strategies to control the dissemination of antibiotic resistance in the environment? A systematic review. *Environ. Evidence* 9, 4.
- Gouliouris, T., Raven, K.E., Moradigaravand, D., Ludden, C., Coll, F., Blane, B., Naydenova, P., Horner, C., Brown, N.M., Corander, J., Limmathurotsakul, D., Parkhill, J., Peacock, S.J., 2019. Detection of vancomycin-resistant *Enterococcus faecium* hospital-adapted lineages in municipal wastewater treatment plants indicates widespread distribution and release into the environment. *Genome Res.* 29, 626–634.
- Gu, C., Karthikeyan, K.G., 2005. Sorption of the antimicrobial ciprofloxacin to aluminum and iron hydrous oxides. *Environ. Sci. Technol.* 39, 9166–9173.
- Guibal, R., Lissalde, S., Brizard, Y., Guibaud, G., 2018. Semi-continuous pharmaceutical and human tracer monitoring by POCS sampling at the watershed-scale in an agricultural rural headwater river. *J. Hazard. Mater.* 360, 106–114.
- Gullberg, E., Albrecht, L.M., Karlsson, C., Sandegren, L., Andersson, D.I., 2014. Selection of a multidrug resistance plasmid by sublethal levels of antibiotics and heavy metals. *mBio* 5, e01918–01914.
- Gullberg, E., Cao, S., Berg, O.G., Ilbäck, C., Sandegren, L., Hughes, D., Andersson, D.I., 2011. Selection of resistant bacteria at very low antibiotic concentrations. *PLoS Pathog.* 7, e1002158.
- Haenni, M., Métayer, V., Jarry, R., Drapeau, A., Puech, M.P., Madec, J.Y., Keck, N., 2020. Wide spread of *bla*_{CTX-M-9}/*mcr-9* IncHI2/ST1 plasmids and CTX-M-9-producing *Escherichia coli* and *Enterobacter cloacae* in rescued wild animals. *Front. Microbiol.* 11, 601317.
- Han, Y., Zhou, Z.C., Zhu, L., Wei, Y.Y., Feng, W.Q., Xu, L., Liu, Y., Lin, Z.J., Shuai, X.Y., Zhang, Z.J., Chen, H., 2019. The impact and mechanism of quaternary ammonium compounds on the transmission of antibiotic resistance genes. *Environ. Sci. Pollut. Res.* 26, 28352–28360.
- Hartmann, A., Amoureux, L., Locatelli, A., Depret, G., Jolivet, C., Gueneau, E., Neuwirth, C., 2012. Occurrence of CTX-M producing *Escherichia coli* in soils, cattle, and farm environment in France (Burgundy Region). *Front. Microbiol.* 3.
- Henriot, C., Martak, D., Cuenot, Q., Loup, C., Masclaux, H., Gillet, F., Bertrand, X., Hocquet, D., Bornette, G., 2019. Occurrence and ecological determinants of the contamination of floodplain wetlands with *Klebsiella pneumoniae* and pathogenic or antibiotic-resistant *Escherichia coli*. *FEMS Microbiol. Ecol.*
- Hernando-Amado, S., Coque, T.M., Baquero, F., Martínez, J.L., 2019. Defining and combating antibiotic resistance from One Health and Global Health perspectives. *Nat. Microbiol.* 4, 1432–1442.
- Heß, S., Berendonk, T.U., Kneis, D., 2018. Antibiotic resistant bacteria and resistance genes in the bottom sediment of a small stream and the potential impact of remobilization. *FEMS Microbiol. Ecol.* 94.
- Hoffman, L.R., D'Argenio, D.A., MacCoss, M.J., Zhang, Z., Jones, R.A., Miller, S.I., 2005. Aminoglycoside antibiotics induce bacterial biofilm formation. *Nature* 436, 1171.
- Houot, S., Pons, M.N., Pradel, M., Caillaud, M.A., Savini, I., Tibi, A., 2014. Valorisation des matières fertilisantes d'origine résiduaire sur les sols à usage agricole ou forestier. Impacts agronomiques, environnementaux, socio-économiques. Expertise scientifique collective, (Inra-CNRS-Irstea (France)).
- Joigneaux, E., 2011. Etat qualitatif des eaux de la nappe du Val d'Orléans : impact du changement climatique et gestion durable de la ressource. Université d'Orléans.
- Jonker, M.T.O., 2021. Effects of sediment manipulation on freely dissolved concentrations of hydrophobic organic chemicals. *Chemosphere* 265, 128694.
- Journal officiel de la République Française, 2015. Arrêté du 22 juillet 2015 relatif aux bonnes pratiques d'emploi des médicaments contenant une ou plusieurs substances antibiotiques en médecine vétérinaire.
- Journal officiel de la République Française, 2016. Article L5132-10 du code de la santé publique.
- Joy, S.R., Bartelt-Hunt, S.L., Snow, D.D., Gilley, J.E., Woodbury, B.L., Parker, D.B., Marx, D.B., Li, X., 2013. Fate and transport of antimicrobials and antimicrobial resistance genes in soil and runoff following land application of swine manure slurry. *Environ Sci Technol* 47 (21), 12801–12808. <https://doi.org/10.1021/es4026358>.
- Jutkina, J., Marathe, N.P., Flach, C.F., Larsson, D.G.J., 2018. Antibiotics and common antibacterial biocides stimulate horizontal transfer of resistance at low concentrations. *Sci. Total Environ.* 616–617, 172–178.
- Karkman, A., Pärnänen, K., Larsson, D.G.J., 2019. Fecal pollution can explain antibiotic resistance gene abundances in anthropogenically impacted environments. *Nat. Commun.* 10, 80.
- Kieffer, N., Nordmann, P., Poirel, L., 2017. *Moraxella* species as potential sources of MCR-like polymyxin resistance determinants. *Antimicrobial Agents Chemother.* 61.
- Klein, E.Y., Van Boeckel, T.P., Martinez, E.M., Pant, S., Gandra, S., Levin, S.A., Goossens, H., Laxminarayan, R., 2018. Global increase and geographic convergence in antibiotic consumption between 2000 and 2015. *Proc. Natl. Acad. Sci.* 115, E3463–E3470.
- Kümmer, K., 2004. Resistance in the environment. *J. Antimicrob. Chemother.* 54, 311–320.
- La Représentation permanente de la France auprès de l'Union Européenne, 2021. La France de l'UE. <https://ue.delegfrance.org/#navigation> (last accessed 24/09/2021).
- Labadie, P., Alligent, S., Berthe, T., Budzinski, H., Bigot-Clivot, A., Collard, F., Dris, R., Gasperi, J., Guignon, E., Petit, F., Rocher, V., Tassin, B., Tramoy, R., Treilles, R., 2019. Contaminants of emerging concern in the Seine River basin: Overview of recent research, vol. 26. In: *The Seine River Basin, The Handbook of Environmental Chemistry*. Springer, Berlin, Heidelberg.
- Laroche, E., Petit, F., Fournier, M., Pawlak, B., 2010. Transport of antibiotic-resistant *Escherichia coli* in a public rural karst water supply. *J. Hydrol.* 392, 12–21.
- Lau, C.H.F., van Engelen, K., Gordon, S., Renaud, J., Topp, E., 2017. Novel antibiotic resistance determinants from agricultural soil exposed to antibiotics widely used in human medicine and animal farming. *Appl. Environ. Microbiol.* 83.
- Le Devendec, L., Mourand, G., Bougeard, S., Léaustic, J., Jouy, E., Keita, A., Couet, W., Rousset, N., Kempf, I., 2016. Impact of colistin sulfate treatment of broilers on the

- presence of resistant bacteria and resistance genes in stored or composted manure. *Vet. Microbiol.* 194, 98–106.
- Leclercq, R., Oberlé, K., Galopin, S., Cattoir, V., Budzinski, H., Petit, F., 2013. Changes in enterococcal populations and related antibiotic resistance along a medical center-wastewater treatment plant-river continuum. *Appl. Environ. Microbiol.* 79, 2428–2434.
- Li, J., Wilkinson, J.L., Boxall, A.B.A., 2021. Use of a large dataset to develop new models for estimating the sorption of active pharmaceutical ingredients in soils and sediments. *J. Hazard. Mater.* 415, 125688.
- Lopatkin, A.J., Meredith, H.R., Srimani, J.K., Pfeiffer, C., Durrett, R., You, L., 2017. Persistence and reversal of plasmid-mediated antibiotic resistance. *Nat. Commun.* 8, 1689.
- Lopez, B., Ollivier, P., Togola, A., Baran, N., Ghestem, J.P., 2015. Screening of French groundwater for regulated and emerging contaminants. *Sci. Total Environ.* 518–519, 562–573.
- Mailler, R., Gasperi, J., Coquet, Y., Deshayes, S., Zedek, S., Cren-Olive, C., Cartiser, N., Eudes, V., Bressy, A., Caupos, E., Moilleron, R., Chebbo, G., Rocher, V., 2015. Study of a large scale powdered activated carbon pilot: Removals of a wide range of emerging and priority micropollutants from wastewater treatment plant effluents. *Water Res.* 72, 315–330.
- Martak, D., Henriot, C.P., Broussier, M., Couchoud, C., Valot, B., Richard, M., Couchot, J., Bornette, G., Hocquet, D., Bertrand, X., 2020. High prevalence of human-associated *Escherichia coli* in wetlands located in eastern France. *Front. Microbiol.* 11.
- McKinney, C.W., Dungan, R.S., Moore, A., Leytem, A.B., 2018. Occurrence and abundance of antibiotic resistance genes in agricultural soil receiving dairy manure. *FEMS Microbiol. Ecol.* 94.
- Melnyk, A.H., Wong, A., Kassen, R., 2015. The fitness costs of antibiotic resistance mutations. *Evol. Appl.* 8, 273–283.
- Menz, J., Muller, J., Olsson, O., Kummerer, K., 2018. Bioavailability of antibiotics at soil-water interfaces: A comparison of measured activities and equilibrium partitioning estimates. *Environ. Sci. Technol.* 52, 6555–6564.
- Meredith, H.R., Srimani, J.K., Lee, A.J., Lopatkin, A.J., You, L., 2015. Collective antibiotic tolerance: Mechanisms, dynamics and intervention. *Nat. Chem. Biol.* 11, 182.
- Middleton, J.H., Salierno, J.D., 2013. Antibiotic resistance in triclosan tolerant fecal coliforms isolated from surface waters near wastewater treatment plant outflows (Morris County, NJ, USA). *Ecotoxicol. Environ. Saf.* 88, 79–88.
- Milakovici, M., Vestergaard, G., González-Plaza, J.J., Petric, I., Šimatović, A., Senta, I., Kublik, S., Schloter, M., Smalla, K., Udiković-Kolić, N., 2019. Pollution from azithromycin-manufacturing promotes macrolide-resistance gene propagation and induces spatial and seasonal bacterial community shifts in receiving river sediments. *Environ. Int.* 123, 501–511.
- Moraru, R., Pourcher, A.M., Jadas-Hécart, A., Kempf, I., Ziebal, C., Kervarrec, M., Comunal, P.Y., Mares, M., Dabert, P., 2012. Changes in concentrations of fluorquinolones and of ciprofloxacin-resistant *Enterobacteriaceae* in chicken feces and manure stored in a heap. *J. Environ. Qual.* 43, 754–763.
- Moulin, G., Cavalié, P., Pellanne, I., Chevance, A., Laval, A., Millemann, Y., Colin, P., Chauvin, C., 2008. A comparison of antimicrobial usage in human and veterinary medicine in France from 1999 to 2005. *J. Antimicrob. Chemother.* 62, 617–625.
- Munkholm, L., Rubin, O., Bækkeskov, E., Humboldt-Dachroeden, S., 2021. Attention to the Tripartite's one health measures in national action plans on antimicrobial resistance. *J. Public Health Policy* 42, 236–248.
- Murray, A.K., Stanton, I., Gaze, W.H., Snape, J., 2021. Dawning of a new ERA: Environmental Risk Assessment of antibiotics and their potential to select for antimicrobial resistance. *Water Res.* 200, 117233.
- Murray, A.K., Stanton, I.C., Wright, J., Zhang, L., Snape, J., Gaze, W.H., 2020. The 'SElection End points in Communities of bacTeria' (SELECT) method: a novel experimental assay to facilitate risk assessment of selection for antimicrobial resistance in the environment. *Environ. Health Perspect.* 128, 107007.
- Murray, A.K., Zhang, L., Snape, J., Gaze, W.H., 2019. Comparing the selective and co-selective effects of different antimicrobials in bacterial communities. *Int. J. Antimicrob. Agents.*
- Nalca, Y., Jänsch, L., Bredenbruch, F., Geffers, R., Buer, J., Häussler, S., 2006. Quorum-sensing antagonistic activities of azithromycin in *Pseudomonas aeruginosa* PAO1: A global approach. *Antimicrob. Agents Chemother.* 50, 1680–1688.
- Nazaret, S., 2020a. Concentrations en ATB dans des PRO et des sols - Projet DABARES.
- Nazaret, S., 2020b. Concentrations en ATB dans des PRO et des sols - Projet QualiAgro.
- Nesme, J., Simonet, P., 2015. The soil resistome: A critical review on antibiotic resistance origins, ecology and dissemination potential in telluric bacteria. *Environ. Microbiol.* 17, 913–930.
- Nishino, K., Nikaido, E., Yamaguchi, A., 2007. Regulation of multidrug efflux systems involved in multidrug and metal resistance of *Salmonella enterica* serovar Typhimurium. *J. Bacteriol.* 189, 9066–9075.
- Nunan, N., Ritz, K., Crabb, D., Harris, K., Wu, K., Crawford, J.W., Young, I.M., 2001. Quantification of the *in situ* distribution of soil bacteria by large-scale imaging of thin sections of undisturbed soil. *FEMS Microbiol. Ecol.* 37, 67–77.
- O'Neill, J., 2014. Antimicrobial Resistance: tackling a crisis for the health and wealth of nations. The review on antimicrobial resistance. https://amr-review.org/sites/default/files/AMR%20Review%20Paper%20-%20Tackling%20a%20crisis%20for%20the%20health%20and%20wealth%20of%20nations_1.pdf (last accessed, March 2021).
- Oberlé, K., Capdeville, M.-J., Berthe, T., Budzinski, H., Petit, F., 2012. Evidence for a complex relationship between antibiotics and antibiotic-resistant *Escherichia coli*: From medical center patients to a receiving environment. *Environ. Sci. Technol.* 46, 1859–1868.
- Olds, H.T., Corsi, S.R., Dila, D.K., Halmo, K.M., Bootsma, M.J., McLellan, S.L., 2018. High levels of sewage contamination released from urban areas after storm events: A quantitative survey with sewage specific bacterial indicators. *PLoS Med.* 15, e1002614.
- Ory, J., Bricheux, G., Togola, A., Bonnet, J.L., Donnadiou-Bernard, F., Nakusi, L., Forestier, C., Traore, O., 2016. Ciprofloxacin residue and antibiotic-resistant biofilm bacteria in hospital effluent. *Environ. Pollut.* 214, 635–645.
- Pal, C., Asiani, K., Arya, S., Rensing, C., Stekel, D.J., Larsson, D.G.J., Hobman, J.L., 2017. Chapter seven - Metal resistance and its association with antibiotic resistance. In: Poole, R.K. (Ed.), *Advances in Microbial Physiology*. Academic Press, pp. 261–313.
- Patrolecco, L., Rauseo, J., Ademollo, N., Grenni, P., Cardoni, M., Levantesi, C., Luprano, M.L., Caracciolo, A.B., 2018. Persistence of the antibiotic sulfamethoxazole in river water alone or in the co-presence of ciprofloxacin. *The Science of the total environment* 640–641, 1438–1446.
- Pérez-Valdespino, A., Pircher, R., Pérez-Domínguez, C.Y., Mendoza-Sanchez, I., 2021. Impact of flooding on urban soils: Changes in antibiotic resistance and bacterial community after Hurricane Harvey. *Sci. Total Environ.* 766, 142643.
- Perrodin, Y., Christine, B., Sylvie, B., Alain, D., Jean-Luc, B.K., Cecile, C.O., Audrey, R., Elodie, B., 2013. A priori assessment of ecotoxicological risks linked to building a hospital. *Chemosphere* 90, 1037–1046.
- Petit, F., Clermont, O., Delannoy, S., Servais, P., Gourmelon, M., Fach, P., Oberlé, K., Fournier, M., Denamur, E., Berthe, T., 2017. Change in the structure of *Escherichia coli* population and the pattern of virulence genes along a rural aquatic continuum. *Front. Microbiol.* 8.
- Petit, F., Denamur, E., Budzinski, H., Leclercq, R., Favennec, L., Chevé, M., Bussi, M., Féménias, D., Garnier, J., 2012. Projet FLASH : Devenir des antibiotiques, flux de gènes et de bactéries antibiotiques en estuaire de Seine, exposition à l'Homme. (Projet Seine-Aval) 155.
- Pourcher, A.M., Jadas-Hécart, A., Cotinet, P., Dabert, P., Ziebal, C., Le Roux, S., Moraru, R., Heddadj, D., Kempf, I., 2014. Effect of land application of manure from enrofloxacin-treated chickens on ciprofloxacin resistance of *Enterobacteriaceae* in soil. *Sci. Total Environ.* 482–483, 269–275.
- Pruden, A., Larsson, D.G.J., Amézquita, A., Collignon, P., Brandt, K.K., Graham, D.W., Lazorchak, J.M., Suzuki, S., Silley, P., Snape, J.R., Topp, E., Zhang, T., Zhu, Y.-G., 2013. Management options for reducing the release of antibiotics and antibiotic resistance genes to the environment. *Environ. Health Perspect.* 121, 878–885.
- Quintela-Baluja, M., Abouelnaga, M., Romalde, J., Su, J.Q., Yu, Y., Gomez-Lopez, M., Smets, B., Zhu, Y.G., Graham, D.W., 2019. Spatial ecology of a wastewater network defines the antibiotic resistance genes in downstream receiving waters. *Water Res.* 162, 347–357.
- Ramey, A.M., Ahlstrom, C.A., 2020. Antibiotic resistance bacteria in wildlife: perspectives on trends, acquisition and dissemination, data gaps, and future directions. *J. Wildl. Dis.* 56, 1–15.
- Ranjard, L., Richaume, A., 2001. Quantitative and qualitative microscale distribution of bacteria in soil. *Res. Microbiol.* 152, 707–716.
- Ratajczak, M., Laroche, E., Berthe, T., Clermont, O., Pawlak, B., Denamur, E., Petit, F., 2010. Influence of hydrological conditions on the *Escherichia coli* population structure in the water of a creek on a rural watershed. *BMC Microbiol.* 10, 222.
- Ribeiro, A.F., Laroche, E., Hanin, G., Fournier, M., Quillet, L., Dupont, J.P., Pawlak, B., 2012. Antibiotic-resistant *Escherichia coli* in karstic systems: A biological indicator of the origin of fecal contamination? *FEMS Microbiol. Ecol.* 81, 267–280.
- Ross, J., Topp, E., 2015. Abundance of antimicrobial resistance genes in bacteriophage following soil fertilization with dairy manure or municipal biosolids, and evidence for potential transduction. *Appl. Environ. Microbiol.* 81, 7905–7913.
- Rozen, Y., Belkin, S., 2001. Survival of enteric bacteria in seawater. *FEMS Microbiol. Rev.* 25, 513–529.
- Salvia, M.-V., Fieul, M., Vulliet, E., 2015. Determination of tetracycline and fluoroquinolone antibiotics at trace levels in sludge and soil. *Appl. Environ. Soil Sci.* 2015, 1–10.
- Salvia, M.-V., Vulliet, E., Wiest, L., Baudot, R., Cren-Olivé, C., 2012. Development of a multi-residue method using acetonitrile-based extraction followed by liquid chromatography-tandem mass spectrometry for the analysis of steroids and veterinary and human drugs at trace levels in soil. *J. Chromatogr. A* 1245, 122–133.
- San Millan, A., MacLean, R.C., 2017. Fitness costs of plasmids: A limit to plasmid transmission. *Microbiology. Spectrum* 5.
- Santé Publique France, 2017. Surveillance de la consommation des antibiotiques. Réseau ATB-Raisin, France. Résultats 2017. Saint-Maurice : Santé publique France, 2017. 134 p. Disponible à partir de l'URL: www.santepubliquefrance.fr.
- Santé Publique France, Anses, Ansm, L'Assurance maladie, 2019. Antibiotiques et résistance bactérienne: une menace mondiale, des conséquences individuelles. (Santé publique France, Agence nationale de sécurité sanitaire de l'alimentation, de l'environnement et du travail, Agence nationale de sécurité du médicament et des produits de santé et l'Assurance maladie.)
- Schaider, L.A., Rodgers, K.M., Rudel, R.A., 2017. Review of organic wastewater compound concentrations and removal in onsite wastewater treatment systems. *Environ. Sci. Technol.* 51, 7304–7317.
- Servais, P., Passerat, J., 2009. Antimicrobial resistance of fecal bacteria in waters of the Seine river watershed (France). *Sci. Total Environ.* 408, 365–372.
- Sharma, R., Larney, F., Chen, J., Yanke, L., Morrison, M., Topp, E., McAllister, T., Yu, Z., 2009. Selected antimicrobial resistance during composting of manure from cattle administered sub-therapeutic antimicrobials. *J. Environ. Qual.* 38, 567–575.
- Sibley, S.D., Pedersen, J.A., 2008. Interaction of the macrolide antimicrobial clarithromycin with dissolved humic acid. *Environ. Sci. Technol.* 42, 422–428.
- Sidhu, H., O'Connor, G., Ogram, A., Kumar, K., 2019. Bioavailability of biosolids-borne ciprofloxacin and azithromycin to terrestrial organisms: Microbial toxicity and earthworm responses. *Sci. Total Environ.* 650, 18–26.

- Simonet, P., Gardeur-Algros, E. 2012. Etude de la situation naturelle ou après amendement par des molécules antibiotiques de la diversité des gènes de résistance à des antibiotiques dans le génome des bactéries telluriques, de leur prévalence dans le sol et de leurs potentialités de transfert horizontal - Projet "Générique". In: *Projet Ademe*.
- Singer, A.C., Shaw, H., Rhodes, V., Hart, A., 2016. Review of antimicrobial resistance in the environment and its relevance to environmental regulators. *Front. Microbiol.* 7, 1728.
- Slekovec, C., Plantin, J., Cholley, P., Thouverez, M., Talon, D., Bertrand, X., Hocquet, D., 2012. Tracking down antibiotic-resistant *Pseudomonas aeruginosa* isolates in a wastewater network. *PLoS ONE* 7, e49300.
- Stalder, T., Barraud, O., Jové, T., Casellas, M., Gaschet, M., Dagot, C., Ploy, M.-C., 2014. Quantitative and qualitative impact of hospital effluent on dissemination of the integron pool. *ISME J.* 8, 768–777.
- Tamtam, F., Le Bot, B., Dinh, T., Mompelat, S., Eurin, J., Chevreuil, M., Bonté, P., Mouchel, J.-M., Ayrault, S., 2011a. A 50-year record of quinolone and sulphonamide antimicrobial agents in Seine River sediments. *J. Soils Sediments* 11, 852–859.
- Tamtam, F., Lebot, B., Eurin, J., Mercier, F., Desportes, A., Chevreuil, M., 2009. Contamination des eaux de surface en milieu rural par des résidus d'antibiotiques. *Eur. J. Water Qual.* 40, 175–186.
- Tamtam, F., Mercier, F., Le Bot, B., Eurin, J., Tuc Dinh, Q., Clément, M., Chevreuil, M., 2008. Occurrence and fate of antibiotics in the Seine River in various hydrological conditions. *Sci. Total Environ.* 393, 84–95.
- Tamtam, F., van Oort, F., Le Bot, B., Dinh, T., Mompelat, S., Chevreuil, M., Lamy, I., Thiry, M., 2011b. Assessing the fate of antibiotic contaminants in metal contaminated soils four years after cessation of long-term waste water irrigation. *Sci. Total Environ.* 409, 540–547.
- Tandukar, M., Oh, S., Tezel, U., Konstantinidis, K.T., Pavlostathis, S.G., 2013. Long-term exposure to benzalkonium chloride disinfectants results in change of microbial community structure and increased antimicrobial resistance. *Environ. Sci. Technol.* 47, 9730–9738.
- Ter Kuile, B.H., Kraupner, N., Bruil, S., 2016. The risk of low concentrations of antibiotics in agriculture for resistance in human health care. *FEMS Microbiol. Lett.* 363.
- Thiebault, T., Alliot, F., Berthe, T., Blanchoud, H., Petit, F., Guigon, E., 2021. Record of trace organic contaminants in a river sediment core: From historical wastewater management to historical use. *Sci. Total Environ.* 773, 145694.
- Thiebault, T., Chassiot, L., Fougère, L., Destandau, E., Simonneau, A., Van Beek, P., Souhaut, M., Chapron, E., 2017. Record of pharmaceutical products in river sediments: A powerful tool to assess the environmental impact of urban management? *Anthropocene* 18, 47–56.
- Tien, Y.C., Li, B., Zhang, T., Scott, A., Murray, R., Sabourin, L., Marti, R., Topp, E., 2017. Impact of dairy manure pre-application treatment on manure composition, soil dynamics of antibiotic resistance genes, and abundance of antibiotic-resistance genes on vegetables at harvest. *Sci. Total Environ.* 581–582, 32–39.
- Törneke, K., Torren-Edo, J., Grave, K., Mackay, D.K., 2015. The management of risk arising from the use of antimicrobial agents in veterinary medicine in EU/EEA countries - a review. *J. Vet. Pharmacol. Ther.* 38, 519–528.
- Um, M.M., Barraud, O., Kérouédan, M., Gaschet, M., Stalder, T., Oswald, E., Dagot, C., Ploy, M.-C., Brugère, H., Bibbal, D., 2016. Comparison of the incidence of pathogenic and antibiotic-resistant *Escherichia coli* strains in adult cattle and veal calf slaughterhouse effluents highlighted different risks for public health. *Water Res.* 88, 30–38.
- Van Boeckel, T.P., Brower, C., Gilbert, M., Grenfell, B.T., Levin, S.A., Robinson, T.P., Teillant, A., Laxminarayan, R., 2015. Global trends in antimicrobial use in food animals. *Proc. Natl. Acad. Sci.* 112, 5649–5654.
- van Elsland, J.D., Semenov, A.V., Costa, R., Trevors, J.T., 2011. Survival of *Escherichia coli* in the environment: fundamental and public health aspects. *ISME J.* 5, 173–183.
- Varela, A.R., Ferro, G., Vredenburg, J., Yanik, M., Vieira, L., Rizzo, L., Lameiras, C., Manaia, C.M., 2013. Vancomycin resistant enterococci: From the hospital effluent to the urban wastewater treatment plant. *Sci. Total Environ.* 450–451, 155–161.
- Vega, N.M., Gore, J., 2014. Collective antibiotic resistance: mechanisms and implications. *Curr. Opin. Microbiol.* 21, 28–34.
- Vittecoq, M., Godreuil, S., Prugnotte, F., Durand, P., Brazier, L., Renaud, N., Arnal, A., Aberkane, S., Jean-Pierre, H., Gauthier-Clerc, M., Thomas, F., Renaud, F., 2016. Antimicrobial resistance in wildlife. *J. Appl. Ecol.* 53, 519–529.
- Vittecoq, M., Laurens, C., Brazier, L., Durand, P., Elguero, E., Arnal, A., Thomas, F., Aberkane, S., Renaud, N., Prugnotte, F., Solassol, J., Jean-Pierre, H., Godreuil, S., Renaud, F., 2017. VIM-1 carbapenemase-producing *Escherichia coli* in gulls from southern France. *Ecol. Evol.* 7, 1224–1232.
- Vivant, A.-L., Garmyn, D., Gal, L., Hartmann, A., Piveteau, P., 2015. Survival of *Listeria monocytogenes* in soil requires agrA-mediated regulation. *Appl. Environ. Microbiol.* 81, 5073–5084.
- Vos, M., Sibley, L., Lo, L.K., Hesse, E., Gaze, W., Klümper, U., 2020. Zinc can counteract selection for ciprofloxacin resistance. *FEMS Microbiol. Lett.* 367.
- Vulliet, E., Cren-Olivé, C., Grenier-Loustalot, M.-F., 2011. Occurrence of pharmaceuticals and hormones in drinking water treated from surface waters. *Environ. Chem. Lett.* 9, 103–114.
- Werner, J.J., Arnold, W.A., McNeill, K., 2006. Water hardness as a photochemical parameter: Tetracycline photolysis as a function of calcium concentration, magnesium concentration, and pH. *Environ. Sci. Technol.* 40, 7236–7241.
- WHO, 2021. WHO integrated global surveillance on ESBL-producing *E. coli* using a "One Health" approach: implementation and opportunities. World Health Organization, Geneva.
- WHO, OIE, FAO, 2020. International instruments on the use of antimicrobials across the human, animal and plant sectors.
- Wiest, L., Chonova, T., Berge, A., Baudot, R., Bessueille-Barbier, F., Ayouni-Derouiche, L., Vulliet, E., 2018. Two-year survey of specific hospital wastewater treatment and its impact on pharmaceutical discharges. *Environ. Sci. Pollut. Res.* 25, 9207–9218.
- World Health Organization, 2015. Global action plan on antimicrobial resistance.
- Worldbank 2019. GDP per capita - France.
- Wright, G.D., 2005. Bacterial resistance to antibiotics: Enzymatic degradation and modification. *Adv. Drug Deliv. Rev.* 57, 1451–1470.
- Zhang, Y., Boyd, S.A., Teppen, B.J., Tiedje, J.M., Zhang, W., Zhu, D., Li, H., 2018. Bioavailability of tetracycline to antibiotic resistant *Escherichia coli* in water-clay systems. *Environ. Pollut.* 243, 1078–1086.
- Zhao, Y., Cocerva, T., Cox, S., Tardif, S., Su, J.-Q., Zhu, Y.-G., Brandt, K.K., 2019. Evidence for co-selection of antibiotic resistance genes and mobile genetic elements in metal polluted urban soils. *Sci. Total Environ.* 656, 512–520.
- Zhu, Y.G., Zhao, Y., Zhu, D., Gillings, M., Penuelas, J., Ok, Y.S., Capon, A., Banwart, S., 2019. Soil biota, antimicrobial resistance and planetary health. *Environ. Int.* 131, 105059.

Further reading

- Gillings, M.R., Gaze, W.H., Pruden, A., Smalla, K., Tiedje, J.M., Zhu, Y.-G., 2015. Using the class 1 integron-integrase gene as a proxy for anthropogenic pollution. *ISME J.* 9 (6), 1269–1279.